



Research Article

Early imperialism in the Andes: Wari colonisation of Nasca

Christina A. Conlee^{1,*} , Corina M. Kellner², Chester P. Walker³ & Aldo Noriega⁴


¹ Department of Anthropology, Texas State University, USA

² Department of Anthropology, Northern Arizona University, USA

³ Archaeo-Geophysical Associates, Austin, USA

⁴ Universidad Nacional Mayor de San Marcos, Lima, Peru

* Author for correspondence ✉ cconlee@txstate.edu



The highland Wari (AD 600–1000) were an influential and expansive Andean civilisation, yet the nature and organisation of Wari power is debated. For example, it is suggested that coastal Nasca was governed by Wari, but doubts remain about its role in the region. Recent excavations at Huaca del Loro in Nasca have uncovered rectilinear compounds, a D-shaped temple, a large cemetery and a domestic area. The authors suggest that this evidence reflects Wari colonisation, undertaken during a period of primary expansion, on a site with long-established ties between Wari and Nasca. The use of multiple colonising strategies and local responses may reflect imperial situations in other world civilisations.

Keywords: Andes, Wari, Nasca, colony, imperialism, architecture

Introduction

Wari (AD 600–1000) was the largest pre-Inca civilisation in the Andes. Despite years of research on Wari, debate continues concerning its political organisation, degree of power and relationship to other societies. The central disagreement concerns whether Wari was an empire (Lumbreras 1974; Isbell & McEwan 1991; Schreiber 1992; Williams & Isla 2002) or an interregional interaction sphere (Shady Solís 1988; Topic & Topic 2000; Jennings 2006; Owen 2010). We argue here that, while Wari greatly facilitated and increased interregional interaction and trade, it was an empire, and that its control of coastal areas has been underestimated. Long proposed to have been governed by Wari (Menzel 1964), coastal Nasca contains Wari sites and artefacts, but doubts remain about Wari's role in the region.

Received: 3 August 2020; Revised: 29 December 2020; Accepted: 13 January 2021

© The Author(s), 2021. Published by Cambridge University Press on behalf of Antiquity Publications Ltd. This is an Open Access article, distributed under the terms of the Creative Commons Attribution licence (<https://creativecommons.org/licenses/by/4.0/>), which permits unrestricted re-use, distribution, and reproduction in any medium, provided the original work is properly cited.

Here, we report the results of new excavations at Huaca del Loro in Nasca. Three hypotheses are investigated: was the site a Wari colony, a local settlement interacting with Wari, or a place established to resist Wari control? Our research is part of the resurgence of imperial studies that prioritises bottom-up, agent-oriented perspectives, and questions a uniform view of empires (see Boozer *et al.* 2020). The relationship between Wari and Nasca is key to understanding broader processes that took place in other ancient empires, including the formation and expansion of first-generation empires, strategies and negotiations used by both empires and the communities that they attempted to dominate, and the transformation and resilience of local societies in colonisation contexts.

Wari and Nasca

Wari developed out of the Huarpa Culture of the Early Intermediate period (AD 1–600) in the Ayacucho region of the Central Highlands of Peru (Figure 1) (Leoni 2009). By the Middle Horizon (AD 600–1000), the capital city of Wari covered almost 15km², with an estimated population of 40 000 (Isbell 2004a: 203). The city contained distinctive architecture, including large orthogonal, rectilinear compounds with central patios,




Figure 1. Map of Nasca drainage, with sites mentioned in the text and inset showing the capital city of Wari (figure by C.A. Conlee).

D-shaped temples and elaborate tombs. To support its large population, agricultural production intensified over time through terracing and irrigation systems (Ochatoma Paravicino & Cabrera Romero 2001). By the mid-eighth century the Wari-controlled area had expanded into much of highland Peru and parts of the coasts, covering up to 320 000km² (Schreiber 2012: 39). In many areas, Wari built distinct settlements that served as seats of regional political power, economic and trade centres, storage facilities, and ritual and feasting locations (Schreiber 1992; McEwan 2005; Nash 2012). Roads, including one through Nasca, connected major sites and resources (Schreiber 1984: 89). Pottery, textiles, obsidian, *Spondylus* shell and new metals made from copper alloys (e.g. Pillsbury 1996; Burger *et al.* 2000; Lechtman 2003) circulated through Wari trade networks. Yet, despite evidence that Wari was an expansive civilisation, there remains a reluctance to call it an empire.

Ayacucho-Nasca connections extend back to the Huarpa Culture, which adopted aspects of Nasca iconography and ceramic technology (Menzel 1964; Benavides Calle 1971; Knobloch 1983; Proulx 2006). At the end of the Early Intermediate period, a time of increasing aridity on the desert coast, some Nasca people (including artisans) possibly moved into the highlands, where conditions were more favourable (Schreiber 2005: 247; Eitel & Mächtle 2009: 27). Indeed, mitochondrial DNA data support such a migration into the highlands *c.* AD 640 (Fehren-Schmitz *et al.* 2014). Pottery styles flowed both ways, as evidenced by the inclusion of Wari-style elements in local Middle Horizon Nasca pottery (called Loro after the type-site Huaca del Loro). Also important to Wari expansion was religion, which included ancestor worship and rituals involving trophy heads (Cook 2001; Ochatoma Paravicino & Cabrera Romero 2002; Tung 2012). The trophy heads were possibly popularised through Nasca influence, as the practice was widespread on the south coast before the Middle Horizon, although they were made and used differently in the two regions (Williams *et al.* 2001; Kellner 2006; Conlee *et al.* 2009; Knudson *et al.* 2009; Tung 2012).

Wari presence in Nasca is evidenced by the colonies, new mortuary practices, changes in local settlements, Wari pottery and other highland imports. Over 40 Wari-affiliated sites have been identified in the *cabezadas* (relatively gently sloping terrains in steep valley locations) zone between 2000 and 4000m asl, including Huayuncalla and Incawasi (Figure 1; Edwards & Schreiber 2014; Isla Cuadrado & Reindel 2014; Sossna 2014). These settlements contain rectangular compounds and Wari pottery, and one (Pacapacari) has two D-shaped temples. None has defensive walls or any evidence for conflict (Sossna 2014: 196). In the lower valley, the site of Pacheco was an important ritual location, and probable colony, yielding oversized, highly decorated pots that were deliberately broken and deposited—similar to those found at Conchopata near the Wari capital (Menzel 1964; Tello 2002; Schreiber 2005). Pataraya, situated between Pacheco and the cabezadas, was a small Wari site near an ancient road linking the coast to the highlands, probably established to facilitate and control trade (Edwards & Schreiber 2014). Located at a similar elevation, Lambrasniyoq has rectilinear compounds and a D-shaped temple (Isla Cuadrado & Reindel 2014).

Loro pottery is the most prevalent type at both Wari and local Nasca sites. Loro (previously called Nasca 8; Menzel 1964) is connected stylistically to Late Nasca pottery (Nasca 7) and to that from Ayacucho (Knobloch 1983; Silverman 1988). Loro was thought to date to the first two phases of the Middle Horizon, although it is documented at sites in Nasca that range from AD 550–920 and is often associated with Nasca 7 pottery and/or the

Chakipampa and Viñaque Wari styles (Menzel 1964; Unkel *et al.* 2012; Sossna 2014; Conlee 2016; Edwards 2017; Kerchusky 2018). Evidence of highland connections include the presence of greater quantities of obsidian from the Quispisisa source that was probably under Wari control, as well as highland-style textiles and objects of copper alloys, including bronze *tupu* pins (Isla Cuadrado 2009; Conlee 2016).

Wari-style mausoleums containing multiple burials and high-status grave goods are common at both local and Wari settlements in Nasca. These replaced the individual interments of the previous period (Ochatoma Paravicino & Cabrera Romero 2001; Isbell & Cook 2002; Isbell 2004b; Isla Cuadrado 2009; Conlee 2011). Oxygen and strontium isotopic analyses have identified two non-local individuals buried in the mausoleums at La Tiza. Both are women in their early twenties, who may have married into the community to create ties between local elites and Wari (Conlee *et al.* 2009; Buzon *et al.* 2012). Preliminary strontium analysis of individuals from the Pataraya tombs indicates that some of the population may have come from the Wari heartland. Increased variation in cranial vault modification styles, including annular styles, also indicates migration (Kellner 2002; Buzon *et al.* 2012). Close to Wari settlements, diet shifted towards maize, but in the far southern Las Trancas Valley, the average diet remained unchanged. Even so, a small subsection of the population consumed less meat and more potatoes and beans, suggesting a strain on maize agriculture (Kellner & Schoeninger 2008). Disease increased slightly and those buried with Wari ceramics exhibit more trauma (Kellner 2002). In sum, Nasca archaeological evidence indicates a close relationship with Wari dating back to the Early Intermediate period Huarpa Culture. In the Middle Horizon several Wari colonies were established, the import of highland goods increased and non-local individuals were present.

Huaca del Loro

Huaca del Loro plays a central role in interpretations of the Middle Horizon in Nasca. Spanning at least 20ha, the site is located in the Las Trancas Valley—the southernmost valley of the Nasca drainage—at 600m asl. Sand covers many of the architectural remains and protects parts of the settlement. At least eight functioning *puquios* (horizontal wells) were operational in the valley during the Middle Horizon (Schreiber & Lancho Rojas 2003: 115), making it a productive agricultural area. Five kilometres east is Zorropata, a 3ha site occupied in the late Early Intermediate period and the early Middle Horizon (AD 416–765), with ceremonial, burial and domestic areas (Kerchusky 2018). Seven trophy heads in the local Nasca style were recovered at Zorropata; they are mostly of non-local origin, in contrast with other trophy heads found in the region. Concentrations of slingstones and a system of walls along the western and southern areas indicate the importance of defence.

Previous research

Huaca del Loro was first identified by a team led by Julio C. Tello in 1927, and was named Tambo de Kopara (Tello 2002: 94–95). Toribio Mejía, who conducted most of the fieldwork, created four field maps and identified three areas (Figure 2). Area A, in the south-west of the site, contained a circular structure and large rectangular compounds, described as the




Figure 2. Map combining Mejía's four field maps (Tello 2002: 16, 18 & 94–95) (figure by E.A. Carmichael).

neighbourhood of the principal *ayllu* (kin group). To the north, area B was defined as the cemetery of the principal *ayllu*, and five tombs (two intact and three looted) were excavated (Tello 2002: 14–24). These large, square tombs were constructed of adobe and stone in the high-status Nasca *barbacoa* style (i.e. roofed with wooden beams). Area C, in the east, had no visible architecture and is interpreted as the neighbourhood of the common people, or secondary *ayllu*. None of the structures recorded on the maps is intact or visible today, except for the round temple and some of the walls of the looted tombs.

A team led by William Duncan Strong (1957) conducted excavations during an expedition in 1952–1953 (Figure 3). Strong renamed the site Huaca del Loro, and defined the Loro ceramic style. Strong's team focused on excavating the round temple, which was built of stone, with a plastered floor and red-painted walls (Strong 1957: 36). Several rooms with thick walls adjoined the temple and contained items such as mummified macaws, fossil whale bones, llama and guinea pig remains and unworked stone monoliths, all of which were interpreted as sacrificial materials. Immediately to the north and east, two large compounds, now destroyed, contained a series of rooms. Strong excavated one compound room (room 1) to the north of the temple and a unit in a nearby midden to the west (cut 1)—the latter now entirely destroyed by modern activity. In the cemetery area north of the compounds, looted, deep rectangular tombs made of semi-cylindrical adobe bricks




Figure 3. Strong's map of Huaca del Loro (1957: fig. 16) (map redrawn by E.A. Carmichael).

were recorded, some with painted walls. Strong (1957: tab. 4) obtained two radiocarbon dates of AD 755±80 and 985±70 (uncorrected) from the temple area.


Paulsen (1983) re-analysed Strong's work, and argued that Huaca del Loro was a highland colony, as circular, stone buildings are characteristic of the highlands rather than the coast. She proposed that the temple represented Huarpa expansion (Paulsen 1983: 104). The round temple has similarities to a late Huarpa ceremonial building at Ñawinpukyo in the Wari heartland (Leoni 2009: fig. 2) and to a large, circular funerary structure with a central square chamber at Huayuncalla (Sossna 2014: 47). Cook (2015) proposes that circular structures amid rectilinear architecture represent a Huarpa tradition that led to Wari D-shaped temples. It has further been suggested that Huaca del Loro was an early Wari provincial centre with occupation dating back to Huarpa (Paulsen 1983; Isbell 1997).

Schreiber (1989) recorded Huaca del Loro during a regional survey in the mid-1980s. She estimated that the site covered 15–20ha, noting that only a small fraction had been investigated. Schreiber (1989: fig. 3) reported that an area north-east of the temple had been bulldozed sometime before 1984, and that looting had increased since Strong's investigations. On a regional scale, she found that Middle Horizon settlement was densest in Las Trancas and that Huaca del Loro was the largest site, proposing that it was the centre of a small polity established to escape and resist Wari control (Schreiber 2005).

Current research

Huaca del Loro figures prominently in discussions of Wari expansion in Nasca and the impact on local people. To explore these processes, the current project tests three hypotheses: that Huaca del Loro was 1) a local Nasca settlement; 2) a Wari colony; or 3) a site of resistance. If it was a local settlement, then established practices and material culture would predominate, along with some hybrid Wari/Nasca material. If a Wari colony, we would expect to find imperial architecture (e.g. rectilinear compounds, D-shaped temples, mausoleums), Wari artefacts (e.g. ceramics, textiles, bronze), and large quantities of goods exchanged over long distances (e.g. obsidian, *Spondylus* shell). If a site of resistance, we would anticipate local architecture and goods, a rejection of Wari practices and evidence of conflict and violence.

We defined five sectors through geophysical and surface surveys (Figure 4). Far to the west is sector I, where ground-penetrating radar (GPR) identified subsurface rectangular architecture. Sector II includes the round temple and compounds designated area A by Mejía and excavated by Strong. Sector III is the looted cemetery, with tombs investigated by Tello and Strong. In the central and eastern portion of the site, sectors IV (the western part was Mejía's area C) and V (not previously considered part of the site) contain no visible architectural remains but dense archaeological surface material. The division of sectors IV and V is arbitrary, as the two are not easily distinguishable by surface features or in the geophysical data. During 2019, we focused on sectors I, III and IV; stratigraphic excavations were conducted and material was sieved through a ¼ inch screen. Photogrammetry (Structure from Motion) was used to record contexts and to generate 3D models. Although samples were selected for radiocarbon-dating, results continue to be delayed by the COVID-19 pandemic.



Christina A. Conlee et al.

Figure 4. Map of Huaca del Loro, with sectors, excavation units and inset of structures 1–2 (figure by N.W. Berry).

Excavation was concentrated in sector I, where GPR identified rectangular structures approximately 0.45–0.55m below the surface. Six trenches were dug to locate architectural remains and, once the walls were exposed, the trenches were extended to define the structures and rooms (Table 1). Structure 1 is a rectangular compound with six rooms exposed to date. The architecture is Wari in terms both of layout and construction. The rooms include a large patio, a room with a wooden post and stairway, a narrow gallery and a room containing circular features that may be storage pits or tombs. The walls are double-coursed and constructed of angular and shaped stone, adobe with mud mortar and remnants of white plaster. Floor areas are white and compact, and in various states of preservation. Future fieldwork will expose the rest of the compound and complete the excavation of the rooms.

GPR survey conducted around structure 1 identified a large, round building located immediately to the south. Excavation revealed a clear D-shaped temple (structure 2), 10m in diameter and with 1m-wide walls (Figure 5). The straight side runs north–south and features a 1m-wide doorway opening east. The walls are double-coursed and constructed of angular stones, with clay mortar and white plaster. Excavation, on average to a depth of 0.40m, did not reach the floor level and much of the interior remains to be excavated. It appears that the temple was deliberately filled in and raw cotton placed around the exterior (Figure 6). A bag, possibly containing the mineral limonite (used to make yellow pigment), was placed in a corner where the rectangular compound intersects the temple (K.J. Vaughn *pers. comm.*) (Figure 7). Ceramics found in the temple and compound were predominantly local Loro, with some Viñaque, Chakipampa and Nasca 7 types (Figure 8).

Four units were excavated in sector III. This extensively looted cemetery contains large adobe and stone walls, with square, chambered tombs. Although no intact burials were excavated, isolated human skeletal elements, in various states of preservation, in units 1, 2, 6 and 7 represent a total of seven adults and one juvenile. Unit 2 consisted of a looted tomb containing at least five adults, including one trophy head of a young adult male (Figure 9). With a ‘mask’ style, a frontal hole made at the glabella and no cranial vault modification, this example resembles Nasca rather than Wari trophy heads (Williams *et al.* 2001; Kellner 2006; Tung 2012). Other individuals exhibit the typical Nasca fronto-occipital cranial vault modification style. Local pottery, along with local-style cranial modification and ‘mask’ trophy head, suggests that the individuals buried in the mausoleum style—a practice introduced through Wari influence—were of local origin.

Three units and one profile were excavated in sector IV, which comprises a large area covered with sand and dense cultural material. Profile 1 and unit 4 yielded the remains of *quincha* walls made of tied cane and probably mud (i.e. wattle and daub) (Figure 10). Used extensively at Middle Horizon Zorropata to the east, *quincha* structures can be built quickly and are commonly found at local Nasca sites. Material excavated was consistent with domestic areas and contained local Loro ceramics. Overall, the excavations in this sector indicate the presence of local people using established construction techniques and pottery. The areas tested were, however, limited, and future excavations will explore whether this sector housed local people who worked for Wari, or whether it belongs to an earlier phase, the local people having left or being forced out when the Wari colony was established. Alternatively, this sector may contain yet undiscovered Wari architectural remains.

Table 1. Areas excavated at Huaca del Loro during the 2019 field season.

Sector	Excavation area	Size (m)	Levels	Depth (m)	Location	Features
I	Trench 1	8 × 2	A–D	0.40	Compound: rooms 2–3	Wooden post; <i>spondylus</i>
I	Trench 2	8 × 2	A–D	0.40	Compound: rooms 1 & 3	Ramp
I	Trench 3	8 × 2	A–D	0.41	Compound: rooms 2–3	Stairway
I	Trench 4	8 × 2	A–D	0.21	Compound: rooms 1 & 4	Wooden post
I	Trench 5	8 × 2	A–C	0.20	Compound: rooms 4–6	Round depressions; plaster
I	Trench 6	10 × 2	A–D	0.20	D-temple; compound: room 4	
I	South extension	6 × 6	A–D	0.53	D-temple; compound: rooms 3–4	Bag of limonite
I	South A extension	5 × 3	A–C	0.50	D-temple	Temple doorway
I	South B extension	5 × 3 × 2 × 1 × 3	A–C	0.20	D-temple	
I	West extension	6 × 6	A–C	0.27	D-temple; compound: room 4	
I	West A extension	6 × 2	A–C	0.31	Compound: room 4	
I	NW extension	6 × 4	A–C	0.20	Compound: rooms 5–6	
I	SW extension	8 × 7	A–C	0.40	D-temple	
III	Unit 1	2 × 2	A–C	0.80	Cemetery	
III	Unit 2	3 × 3 (1.3 × 0.5 & 1 × 1 extension)	A–C	0.80	Looted adobe-and-cobble tomb	Trophy head
III	Unit 6	2 × 2	A–F	0.74	Cemetery, corner of large structure	
III	Unit 7	2 × 2	A–M	1.60	Cemetery, corner of large structure	
IV	Unit 3	4 × 2 (2 × 2 extension)	A	0.84	Disturbed area near bulldozing	Very little cultural material
IV	Unit 4	4 × 2	A–H	0.79	Domestic area	<i>Quincha</i> wall
IV	Unit 5	2 × 2	A	0.76	Disturbed area	Very little cultural material
IV	Profile 1	1.5 × 2	1–8	1.5	Domestic area, along road cut	<i>Quincha</i> wall




Figure 5. Compound (structure 1) and D-shaped temple (structure 2) (figure by B.E. Heisinger).




Figure 6. Cotton along exterior of the Huaca del Loro temple wall and raw cotton (inset) (figure by C.A. Conlee).



Figure 7. Bag containing limonite from the temple at Huaca del Loro (figure by C.A. Conlee).

Wari colonialism in Nasca

The discovery of Wari architecture and artefacts suggests that Huaca del Loro was a colony and that Wari exercised control in a variety of regions, including Nasca and the coast. Several sites in Nasca are now known to feature Wari rectangular architecture, D-shaped structures, and/or imperial pottery and imported goods. Huaca del Loro is the lowest-lying site, one of



Figure 8. a) Left: Viñaque pottery from the south extension; right: Chakipampa and Viñaque pottery from trench 1; b) fragment of Loro face-neck jar from the south-west extension, and Loro bowls from the south extension; c) Loro figurine from the south extension. Details of the contexts can be found in Table 1 and Figure 5 (figure by C.A. Conlee).



Figure 9. Unit 2 and trophy head at Huaca del Loro (image created with the help of B.E. Heisinger).




Figure 10. Unit 4 with quincha wall at Huaca del Loro (figure by B.E. Heisinger).

only a few that contains all of the above characteristics, and the first such site to have been extensively excavated. D-shaped structures are not documented at all Wari sites. Even the immense highland centre of Pikillacta (McEwan 2005) lacks such structures, as does Pataraya (a road station occupied by a small community; Edwards & Schreiber 2014), the only other excavated Wari site in southern Nasca. What makes Huaca del Loro distinctive may be connected to the length or intensity of its occupation, as well as its function. Given that D-shaped structures are interpreted as temples, we can suppose that their construction indicates intensive ritual activity and the presence of religious officials. The placement of offerings of raw cotton around the exterior wall of the temple at Huaca del Loro, as well as its presence in many other contexts, suggests that this coastal product was a focus of Wari interest in the area. If this region was a centre of cotton production, then Huaca del Loro was probably an important economic hub that housed a variety of people. The fact that the site has a large area inhabited by local people constitutes another distinguishing trait. This population may have provided support personnel for the Wari installation, which would have required the presence of various types of administrators and managers, including Wari elites, served by a D-shaped temple.

The chronology of Huaca del Loro has yet to be fully established. Stylistically, the pottery and architecture suggest that it spans the late Early Intermediate period to at least the middle of the Middle Horizon (*c.* AD 550–800). The site appears to be part of an early Wari expansion into Nasca. Refinement of this chronology requires further excavation and modern radiocarbon-dating, which will influence future interpretations. While it appears that Huaca del Loro was not a site of resistance, as had been previously proposed (Schreiber 2005), it is possible that people resisted and were defeated by Wari, who then set up a colony, if the extensive local area of the settlement was occupied before the imperial sector.

Wari was a first-generation (or primary) empire that developed from Indigenous roots, and its organisation and strategies probably differed from those of ‘shadow empires’, such as the Xiongnu of the Mongolian steppe (Barfield 2001) that arose, in part, through contact with neighbouring polities, or of ‘successor empires’ that subsequently developed. The latter include the Inca, who built on Wari organisation and infrastructure (Düring *et al.* 2020; Williams *et al.* 2020). Wari’s earliest colonies, such as those in Nasca, were probably located where the people of Ayacucho had long-established ties. Nasca was incorporated during a period of primary expansion, which, as seen in many empires (e.g. the Assyrian Empire), affects well-known regional corridors (Parker 2020). During primary expansion, empires often spread via existing communication and transport networks, along which are local centres that are taken over to control ‘pockets’ of territory and to protect goods and people in transit (Liverani 1984; Parker 2020). The relationship between Wari and Nasca was complex and strong, extending back to the period before imperial expansion. Nasca was incorporated early into the Wari Empire, probably for both economic and ideological reasons. The Nasca region supplied important coastal crops, such as cotton, and its influential religion involving trophy heads provided a powerful belief system and practices that Wari could have incorporated into its own.

First-generation empires such as Wari probably employed many strategies, even within a single province. Furthermore, they involved many diverse agents, as they were working without a blueprint, experimenting with different types of control and managing a variety of interests. Local people responded and interacted in a range of ways as they negotiated this new type

of external power. Such diversity is evident in Nasca in the different types of settlements established by Wari, and in the variable relationships between Nasca and Wari peoples. The Huaca del Loro colony may have exerted considerable control over the local population, either by employing them or forcing their departure. Nearby Zorropata, without Wari presence and with defensive features, indicates possible warfare with Wari. By contrast, Wari sites farther north show few signs of conflict and include a major religious offering deposit at Pacheco and evidence of intermarriage. Variability of this type can obscure the powerful nature of Wari and may explain why some researchers reject the idea of it being an empire. It is certainly not a unique situation, as this kind of variability can be found in other first-generation empires, such as the Akkadian Empire (e.g. Foster 2016; Schrakamp 2016)—and such variability may be an important factor in the study of other emerging empires.

Acknowledgements

The Peruvian Ministry of Culture granted permission to conduct fieldwork.

Funding statement

The research at Huaca del Loro was funded by the National Science Foundation (grant BCS-1758084), a grant from the Curtiss T. Brennan and Mary G. Brennan Foundation, and the Research Enhancement Program at Texas State University.

References

- BARFIELD, T.J. 2001. The shadow empires: imperial state formation along the Chinese-nomad frontier, in S.E. Alcock, T.N. D'Altory, K.D. Morrison & C.M. Sinopoli (ed.) *Empires: perspectives from archaeology and history*: 10–41. Cambridge: Cambridge University Press.
- BENAVIDES CALLE, M. 1971. Análisis de la cerámica Huarpa. *Revista del Museo Nacional* 37: 63–88.
- BOOZER, A.L., B.S. DÜRING & B.J. PARKER (ed.). 2020. *Archaeologies of empire: local participants and imperial trajectories*. Santa Fe (NM): School for Advanced Research.
- BURGER, R.L., K.L. MOHR-CHÁVEZ & S.J. CHÁVEZ. 2000. Through the glass darkly: prehispanic obsidian procurement and exchange in southern Peru and northern Bolivia. *Journal of World Prehistory* 14: 267–362.
<https://doi.org/10.1023/A:1026509726643>
- BUZON, M.R., C.A. CONLEE, A. SIMONETTI & G.J. BOWEN. 2012. The consequences of Wari contact in the Nasca region during the Middle Horizon: archaeological, skeletal, and isotopic evidence. *Journal of Archaeological Science* 39: 2627–36.
<https://doi.org/10.1016/j.jas.2012.04.003>
- CONLEE, C.A. 2011. An exploration of looted Middle Horizon tombs from Nasca. *Nawpa Pacha* 31: 45–54.
<https://doi.org/10.1179/naw.2011.31.1.45>
- 2016. *Beyond the Nasca lines: ancient life at La Tiza in the Peruvian desert*. Gainesville: University Press of Florida.
- CONLEE, C.A. et al. 2009. Identifying foreigners versus locals in the burial population of Nasca, Peru: an investigation using strontium isotope analysis. *Journal of Archaeological Science* 36: 2755–64.
<https://doi.org/10.1016/j.jas.2009.08.016>
- COOK, A.G. 2001. Huari D-shaped structures, sacrificial offerings, and divine rulership, in E.P. Benson & A.G. Cook (ed.) *Ritual sacrifice in ancient Peru*: 137–64. Austin: University of Texas Press.
- 2015. The shape of things to come: the genesis of Wari wak'as, in T.L. Bray (ed.) *The archaeology of wak'as: explorations in the pre-Columbian Andes*: 295–334. Boulder: University Press of Colorado.
- DÜRING, B.S., A.L. BOOZER & B.J. PARKER. 2020. Archaeologies of empires: an introduction, in A.L. Boozer, B.S. Düring & B.J. Parker (ed.)

- Archaeologies of empire: local participants and imperial trajectories*: 1–20. Santa Fe (NM): School for Advanced Research.
- EDWARDS, M.J. 2017. Ritual practice at the end of empire: evidence of an abandonment ceremony from Pataraya, a Wari outpost on the south coast of Peru, in S.A. Rosenfeld & S.L. Bautista (ed.) *Rituals of the past: prehispanic and colonial case studies in Andean archaeology*: 151–68. Boulder: University Press of Colorado.
- EDWARDS, M.J. & K.J. SCHREIBER. 2014. Pataraya: the archaeology of a Wari outpost in Nasca. *Latin American Antiquity* 25: 215–33.
<https://doi.org/10.7183/1045-6635.25.2.215>
- EITEL, B. & B. MÄCHTLE. 2009. Man and environment in the eastern Atacama Desert (southern Peru): Holocene climate changes and their impact on pre-Columbian cultures, in M. Reindel & G.A. Wagner (ed.) *New technologies for archaeology: multidisciplinary investigations in Palpa and Nasca, Peru*: 17–37. Berlin & Heidelberg: Springer.
https://doi.org/10.1007/978-3-540-87438-6_2
- FEHREN-SCHMITZ, L. et al. 2014. Climate change underlies global demographic, genetic, and cultural transitions in pre-Columbian southern Peru. *Proceedings of the National Academy of Sciences of the USA* 111: 9443–48.
<https://doi.org/10.1073/pnas.1403466111>
- FOSTER, B. 2016. *The age of Agade: inventing empire in ancient Mesopotamia*. New York: Routledge.
- ISELL, W.H. 1997. Reconstructing Huari: a cultural chronology for the capital city, in L.R. Manzanilla (ed.) *Emergence and change in early urban societies*: 181–227. New York: Springer.
https://doi.org/10.1007/978-1-4899-1848-2_8
- 2004a. Palaces and politics in the Andean Middle Horizon, in S.T. Evans & J. Pillsbury (ed.) *Palaces of the ancient new world*: 191–246. Washington, D.C.: Dumbarton Oaks.
- 2004b. Mortuary preferences: a Wari Culture case study from Middle Horizon Peru. *Latin American Antiquity* 15: 3–32.
<https://doi.org/10.2307/4141562>
- ISELL, W.H. & A.G. COOK. 2002. A new perspective on Conchopata and the Andean Middle Horizon, in H. Silverman & W.H. Isbell (ed.) *Andean archaeology II: art, landscape and society*: 249–305. New York: Kluwer.
https://doi.org/10.1007/978-1-4615-0597-6_11
- ISELL, W.H. & G.F. McEWAN (ed.). 1991. *Huari administrative structure: prehistoric monumental architecture and state government*. Washington, D.C.: Dumbarton Oaks.
- ISLA CUADRADO, J. 2009. From hunters to regional lords: funerary practices in Palpa, Peru, in M. Reindel & G.A. Wagner (ed.) *New technologies for archaeology: multidisciplinary investigations in Palpa and Nasca, Peru*: 119–40. Berlin & Heidelberg: Springer.
https://doi.org/10.1007/978-3-540-87438-6_8
- ISLA CUADRADO, J. & M. REINDEL. 2014. La ocupación Wari en los valles de Palpa, costa sur del Perú. *Arqueología y Sociedad* 27: 193–226.
- JENNINGS, J. 2006. Understanding Middle Horizon Peru: hermeneutic spirals, interpretative traditions, and Wari administrative centers. *Latin American Antiquity* 17: 265–85.
<https://doi.org/10.2307/25063053>
- KELLNER, C.M. 2002. Coping with environmental and social challenges in prehistoric Peru: bioarchaeological analyses of Nasca populations. Unpublished PhD dissertation, University of California, Santa Barbara.
- 2006. ‘Trophy’ heads in prehistoric Peru: Wari imperial influence on Nasca head-taking practices, in M. Bonogofsky (ed.) *Skull collection, modification, and decoration* (British Archaeological Reports International Series 1539): 101–12. Oxford: British Archaeological Reports.
- KELLNER, C.M. & M.J. SCHOENINGER. 2008. Wari’s imperial influence on local Nasca diet: the stable isotope evidence. *Journal of Anthropological Archaeology* 27: 226–43.
<https://doi.org/10.1016/j.jaa.2007.12.003>
- KERCHUSKY, S.L.D. 2018. Archaeological investigations at Zorropata: local socioeconomic and political development in a context of imperial Wari expansion. Unpublished PhD dissertation, University of California, Santa Barbara.
- KNOBLOCH, P. J. 1983. A study of the Andean Huari ceramics from the Early Intermediate Period to the Middle Horizon Epoch 1. Unpublished PhD. dissertation, State University of New York, Binghamton.
- KNUDSON, K.J. et al. 2009. The geographic origins of Nasca trophy heads using strontium, oxygen, and carbon isotope data. *Journal of Anthropological Archaeology* 28: 244–57.
<https://doi.org/10.1016/j.jaa.2008.10.006>

- LECHTMAN, H. 2003. Middle Horizon bronze: centers and outliers, in L. van Zelst (ed.) *Patterns and process*: 248–68. Washington, D.C.: Smithsonian Center for Materials Research and Education.
- LEONI, J. B. 2009. *Archaeological investigations at Nawinpukyo: change and continuity in an Early Intermediate Period and Middle Horizon community in Ayacucho, Peru* (British Archaeological Reports International Series 1991). Oxford: British Archaeological Reports. <https://doi.org/10.30861/9781407305257>
- LIVERANI, M. 1984. The growth of the Assyrian Empire in the Habur Middle Euphrates area: a new paradigm. *Annales Archaeologiques de Republique Syrienne* 34: 107–15.
- LUMBRERAS, L. 1974. *The peoples and cultures of ancient Peru*. Washington, D.C.: Smithsonian Institution.
- MC EWAN, G. (ed.). 2005. *Pikillakta: the Wari Empire in Cuzco*. Iowa City: University of Iowa Press. <https://doi.org/10.1525/jlca.2006.11.2.434>
- MENZEL, D. 1964. Style and time in the Middle Horizon. *Nawpa Pacha* 2: 66–105. <https://doi.org/10.1179/naw.1964.2.1.001>
- NASH, D.J. 2012. The art of feasting: building an empire with food and drink, in S.E. Bergh (ed.) *Wari: lords of the ancient Andes*: 82–101. New York: Thames & Hudson and Cleveland Museum of Art.
- OCHATOMA PARAVICINO, J. & M. CABRERA ROMERO. 2001. *Poblados rulaes Huari: una visión desde Ago Wayqo*. Lima: CANO.
- 2002. Religious ideology and military organization in the iconography of a D-shaped ceremonial precinct at Conchopata, in H. Silverman & W.H. Isbell (ed.) *Andean archaeology II: art, landscape and society*: 225–48. New York: Kluwer.
- OWEN, B. 2010. Wari in the Majes-Camaná Valley: a different kind of horizon, in J. Jennings (ed.) *Beyond Wari walls: regional perspectives on Middle Horizon Peru*: 57–78. Albuquerque: University of New Mexico Press.
- PARKER, B.J. 2020. Re-modeling empire, in A.L. Boozer, B.S. During & B.J. Parker (ed.) *Archaeologies of empire: local participants and imperial trajectories*: 229–54. Santa Fe (NM): School for Advanced Research Press.
- PAULSEN, A.C. 1983. Huaca del Loro revisited: the Nasca-Huarpa connection, in D.H. Sandweiss (ed.) *Investigations of the Andean past*: 98–121. Ithaca (NY): Cornell University Latin American Studies Program.
- PILLSBURY, J. 1996. The thorny oyster and the origins of empire: implications of recently uncovered *Spondylus* imagery from Chan Chan, Peru. *Latin American Antiquity* 7: 313–40. <https://doi.org/10.2307/972262>
- PROULX, D. 2006. *A sourcebook of Nasca ceramic iconography: reading a culture through its art*. Iowa City: University of Iowa Press.
- SCHRAKAMP, I. 2016. Akkadian Empire, in J. MacKenzie (ed.) *The encyclopedia of empire*: 1–10. New York: Wiley. <https://doi.org/10.1002/9781118455074.wbeoe395>
- SCHREIBER, K.J. 1984. Prehistoric roads in the Carahuarazo Valley, Peru, in A. Kendall (ed.) *Current archaeological projects in the Central Andes: some approaches and results* (British Archaeological Reports International Series 210): 75–94. Oxford: British Archaeological Reports.
- 1989. On revising Huaca del Loro: a cautionary tale. *Andean Past* 2: 69–79.
- 1992. *Wari imperialism in Middle Horizon Peru* (Anthropological Papers Museum of Anthropology, University of Michigan 87). Ann Arbor: Museum of Anthropology, University of Michigan.
- 2005. Imperial agenda and local agency: Wari colonial strategies, in G.J. Stein (ed.) *The archaeology of colonial encounters: comparative perspectives*: 237–62. Santa Fe (NM): School of American Research.
- 2012. The rise of an Andean empire, in S.E. Bergh (ed.) *Wari: lords of the ancient Andes*: 31–46. New York: Thames & Hudson.
- SCHREIBER, K.J. & J. LANCHO ROJAS. 2003. *Irrigation and society in the Peruvian desert: the puquios of Nasca*. Lanham (MD): Lexington Books.
- SHADY SOLÍS, R. 1988. Epoca Huari como interacción de las sociedades regionales. *Revista Andina* 6: 67–99.
- SILVERMAN, H. 1988. Nasca 8: a reassessment of its chronological placement and cultural significance. *Multidisciplinary Studies in Andean Anthropology* 8: 23–32.
- SOSSNA, V. 2014. Impacts of climate variability on pre-Hispanic settlement behavior in south Peru: the northern Rio Grande de Nasca drainage between 1500 BCE and 1532 CE. Unpublished PhD dissertation, Christian-Albrechts-Universität zu Kiel.

- STRONG, W.D. 1957. Paracas, Nazca and Tiahuanacoid cultural relationships in south coastal Peru. *Memoirs of the Society for American Archaeology* 13: 1–48.
- TELLO, J.C. 2002. *Arqueología de la cuenca del Río Grande de Nasca. Cuadernos de investigación del archivo Tello, 3*. Lima: Museo de Arqueología y Antropología, Universidad Nacional Mayor de San Marcos.
- TOPIC, T. & J.R. TOPIC. 2000. Hacia la comprensión del fenómeno Huari: una perspectiva norteña, in P. Kaulicke & W. Isbell (ed.) *Huari y Tiwanaku: modelos y evidencias, primera parte* (Boletín de Arqueología PUCP 4): 81–217. Lima: Fondo Editorial de la Pontificia Universidad Católica del Perú.
- TUNG, T.A. 2012. *Violence, ritual, and the Wari Empire: a social bioarchaeology of imperialism in the ancient Andes*. Gainesville: University Press of Florida.
<https://doi.org/10.5744/florida/9780813037677.001.0001>
- UNKEL, I. *et al.* 2012. A comprehensive numerical chronology for the pre-Columbian cultures of the Palpa valleys, south coast of Peru. *Journal of Archaeological Science* 39: 2294–303.
<https://doi.org/10.1016/j.jas.2012.02.021>
- WILLIAMS, P.R. & J. ISLA. 2002. Investigaciones arqueológicas en Cerro Baúl, un enclave Wari en el valle de Moquegua. *Gaceta Arqueológica Andina* 26: 87–120.
- WILLIAMS, P.R., D. NASH & S. CHACALTANA. 2020. Wari and Tiwanaku: early imperial repertoires in Andean South America, in A.L. Booser, B.S. Düring & B.J. Parker (ed.) *Archaeologies of empire: local participants and imperial trajectories*: 199–228. Santa Fe (NM): School for Advanced Research.
- WILLIAMS, S., K. FORGEY & E. KLARICH. 2001. An osteological study of Nasca trophy heads collected by A.L. Kroeber during the Marshall field expeditions to Peru. *Fieldiana Anthropology* 33: 1–132.
<https://doi.org/10.5962/bhl.title.5292>