ELSEVIER

Contents lists available at ScienceDirect

Computers in Industry

journal homepage: www.sciencedirect.com/journal/computers-in-industry





Enabling Building Information Model-driven human-robot collaborative construction workflows with closed-loop digital twins

Xi Wang a,1 , Hongrui Yu b,1 , Wes McGee c , Carol C. Menassa b,* , Vineet R. Kamat b

- ^a Department of Construction Science, Texas A&M University, 3337 TAMU, College Station, TX 77843, USA
- b Department of Civil and Environmental Engineering, University of Michigan, 2350 Hayward Street, Ann Arbor, MI 48109, USA
- ^c Taubman College of Architecture and Urban Planning, University of Michigan, 2000 Bonisteel Boulevard, Ann Arbor, MI 48109, USA

ARTICLE INFO

Keywords: Construction robotics Building Information Model Digital twin Human-robot collaboration

ABSTRACT

The introduction of assistive construction robots can significantly alleviate physical demands on construction workers while enhancing both the productivity and safety of construction projects. Leveraging a Building Information Model (BIM) offers a natural and promising approach to driving robotic construction workflows. However, because of uncertainties inherent in construction sites, such as discrepancies between the as-designed and as-built components, robots cannot solely rely on a BIM to plan and perform field construction work. Human workers are adept at improvising alternative plans with their creativity and experience and thus can assist robots in overcoming uncertainties and performing construction work successfully. In such scenarios, it is critical to continuously update the BIM as work processes unfold so that it includes as-built information for the ensuing construction and maintenance tasks. This research introduces an interactive closed-loop digital twin framework that integrates a BIM into human-robot collaborative construction workflows. The robot's functions are primarily driven by the BIM, but it adaptively adjusts its plans based on actual site conditions, while the human co-worker oversees and supervises the process. When necessary, the human co-worker intervenes in the robot's plan by changing the task sequence or workspace geometry or requesting a new motion plan to help the robot overcome the encountered uncertainties. A drywall installation case study is conducted to verify the proposed workflow. In addition, experiments are carried out to evaluate the system performance using an industrial robotic arm in a research laboratory setting that mimics a construction site and in the Gazebo simulation. Integrating the flexibility of human workers and the autonomy and accuracy afforded by the BIM, the proposed framework offers significant promise of increasing the robustness of construction robots in the performance of field construction work.

1. Introduction

Construction has been ill-famed for its dangerous and harsh working environments and excessive physical demands on workers, which often result in a lack of motivation for people, especially those of diverse abilities, to pursue their careers in the industry (Escamilla et al., 2016; Park et al., 2023; Aulin and Jingmond, 2011; Zhang et al., 2023). As a result, the construction industry is facing severe shortages of skilled labor (Kim et al., 2020; Cai et al., 2023). According to the Associated General Contractors of America, 73% of contractors consider worker shortage as their biggest concern in 2022 (AGC, 2022).

Industrial robotic manipulators can exert high physical power and

operate at high speeds, and thus have significant potential to reduce the physical burden on human workers (Brosque et al., 2023). Robots have already been adopted in several industry sectors such as manufacturing, nuclear, healthcare, and rescue to reduce human workers' workload and their exposure to potential hazards (Fu et al., 2023; Barbash and Glied, 2010; Qian et al., 2012; Davids, 2002; Pérez et al., 2019). Construction automation powered by robotics has demonstrated the potential to reduce the physical demand on construction workers and improve the diversity and inclusion of the construction workforce, thus mitigating the labor shortage issues faced by the industry (Davila Delgado et al., 2019; Liang et al., 2021; Rodrigues et al., 2023). On the other hand, while robotics is still in its emerging phase in the field of construction

^{*} Corresponding author.

E-mail address: menassa@umich.edu (C.C. Menassa).

¹ These two authors contributed equally to this work.

automation, the use of Building Information Models (BIMs) has been widely adopted in the industry to support digital construction project workflows (Zhang et al., 2022; Volk et al., 2014).

A BIM is "a digital representation of physical and functional characteristics of a facility" (NIBS, 2015). It contains a variety of geometric and attribute information, such as 3D models, schedules, construction methods, and materials, which are used to facilitate the construction processes (Correa, 2016). Although BIMs play important roles in design, communication, and project management throughout the project life cycle (Zhang et al., 2022; Golabchi et al., 2013), they generally lack the interoperability needed to support construction robot task planning (Correa, 2019; Kim et al., 2021). Currently, robot installation sequences and poses are generated primarily by retrieving geometric data from BIMs encoded using Industry Foundation Classes (IFC) (Correa, 2016; Kim et al., 2021; Ding et al., 2020). However, such proposed approaches are limited to specific construction tasks or types of components, such as bricklaying or wall panels. Moreover, working environments for field construction involve a lot of uncertainties (e.g., deviations in as-built components) that can cause robot failure when following a rigid program. While a BIM can provide information to the robot, the workflow needs the ability to improvise (i.e., dynamically adjust plans based on encountered situations) to flexibly perform the work during the field construction process (Lundeen et al., 2017).

Compared to robots, humans are more adept at creative and adaptive planning based on their experience (Suresh et al., 2019; Sharif et al., 2016). They can adjust a task plan according to what they observe on the construction site to ensure the quality and continuity of the work. Thus, human expertise in improvisation is indispensable for field construction that involves considerable uncertainties and is necessary to support robotic construction (Yoon et al., 2023; Yu et al., 2024). In addition, human workers can supervise the robotic construction process to ensure collision-free safe manipulation in dynamic on-site working environments. Therefore, by enabling Human-Robot Collaboration (HRC), the flexibility and robustness of BIM-driven robotic construction systems can be significantly improved.

This research proposes a closed-loop digital twin framework to enable BIM-driven Human-Robot Collaborative Construction (HRCC) workflows, as shown in Fig. 1. The system is built upon an interactive and immersive process-level digital twin (I2PL-DT) system previously

developed by the authors (Wang et al., 2021). A BIM module is integrated to provide geometric and attribute data to both the human workers through the user interface and the Robot Operating System (ROS). After a robot generates work plans with information from the BIM, human co-workers supervise the robot's workflow (e.g., preview robot plans and monitor execution status) and make interventions (e.g., adjust installation target or request another trajectory plan) when necessary.

In addition, the as-built data collected by the robot during the construction process is sent to the BIM to reflect changes between the asdesigned and the as-built workspace to be used for ensuing construction tasks, thereby closing the loop. The system supports seamless integration of various sources of information received from the BIM, human co-workers, and robot sensors. In parallel, the system processes the collected information in various ways: it converts data into forms that can be visualized and understood by humans, prepares it for computation and control by robots, and saves and presents it within BIMs.

The BIM-driven HRCC processes involve five main steps, including (1) formulation of the BIM repository that supports robotic construction; (2) preparation of the construction site and the BIM for a specific construction activity; (3) automatic digital twin generation; (4) construction execution, including resolution of as-built / as-designed deviations; and (5) updating of the BIM repository with as-built construction data collected by the robot. The technical approach to enable these processes is discussed in Section 3.

A drywall installation case study conducted on a large-scale physical Kuka industrial robotic arm is presented as a proof-of-concept implementation to explore the physical setup process and for system verification (Section 4). In addition, physical and simulation experiments involving block pick-and-place and drywall installation activities are carried out to evaluate system performance and validate the proposed deviation adaptation methods (Section 5). The proposed system not only extends the autonomy and accuracy of robotic construction but also offers the flexibility to overcome uncertainties in field construction work. The presented framework and workflow have the potential to be applied to a broad variety of construction tasks.




Fig. 1. Closed-Loop Digital Twin Framework Overview.

2. Background

2.1. Human-robot collaboration

HRC aims to retain the robustness and adaptability of an automated system by combining robots' computational ability and durability with humans' creativity and flexibility (Tsarouchi et al., 2017; Yu et al., 2023). HRC can be classified into two types, physical collaboration and contactless collaboration (Hentout et al., 2019). For physical HRC, the human co-worker intentionally makes physical contact with the robot or the object held by the robot to hand over or co-manipulate objects (Lee and Moon, 2014; Devadass et al., 2019). However, working alongside robots, especially construction robots that carry large and heavy components, poses high safety risks to humans. Therefore, contactless HRC has been used in many applications. It allows humans to guide robots with gestures (Kim et al., 2009), natural language (Park et al., 2024; She et al., 2014), joysticks and haptic devices (Chotiprayanakul et al., 2012; Zhu et al., 2022), Virtual Reality (VR) (Pérez et al., 2019; Li and Zou, 2023; Adami et al., 2021), and neural signals (Zhang et al., 2023; Liu et al., 2021). One main concern with contactless HRC, especially those from remote locations, is that humans' perception of the operational environment and the robot is limited. It is critical to provide humans with sufficient and accurate information in an effective way to enable efficient decision making. One of the popular approaches is to create a digital twin to provide real-time information about the robot and its operation environment to humans (Malik and Brem, 2021; Wang et al., 2020)

In prior work, the authors proposed an I2PL-DT system for human workers to remotely receive and visualize the updated state of a construction workspace (Wang et al., 2021). The system consists of three modules, including an immersive Virtual Reality (VR) interface, middleware enabled by ROS, and Robot Operation Environment (ROE) (i.e., construction site, robot, and sensors). Human co-workers can visualize construction site and robot conditions in real-time and perform high-level task planning (e.g., indicating component installation sequence and positions). The high-level plan is then used to generate motion plans, which are processed into realistic animations in VR for the human co-worker to preview and evaluate. Upon approval, the robot executes the approved plan under human supervision. The work supports a collaboration paradigm where human workers perform high-level decision-making and supervision while robots undertake low-level motion planning and physical execution of the work.

Despite being a key component of the workflow proposed in this

paper, the previously developed I2PL-DT system, in and of itself, has several limitations. First, the process of creating the digital twin for a construction task takes considerable effort. The immersive VR interface needs to be manually created by importing BIM data into VR, creating interactive game objects, and adding interactive functions (e.g., sending messages to ROS). Second, the human co-worker needs to specify the work plan for each component by indicating to the robot which component to pick up and the location to install it. Thus, substantial human effort is required for such step-by-step instructions. Lastly, since the human co-worker specifies the high-level task objectives by manipulating and placing virtual objects with controllers in VR, the accuracy is limited and the resulting work may not comply with typical construction work specifications and desired tolerances.

In order to overcome these critical and practical limitations, this paper integrates a BIM with the I2PL-DT system and proposes an automatic approach to creating digital twins. Fig. 2 shows the elements of the updated and significantly expanded system presented in this paper and compares it to the previous I2PL-DT system. With the proposed approach, manual processes of creating the digital twin and placing each component step-by-step in VR can be avoided, which improves system autonomy and work accuracy as well as reduces human workers' workload. In the remainder of this section, the adoption of a BIM to support construction automation and robotics, along with the existing approaches to create digital twins for robotic applications, are introduced and discussed.

2.2. BIMs in construction automation and robotics

BIMs have been widely adopted to promote automation throughout the life cycle of the Architecture, Engineering and Construction, and Facilities Management (AEC/FM) industry (Deng et al., 2021). Recently, BIMs have been used to facilitate robotized construction in various ways. For example, BIMs can provide information to guide the off-site prefabrication process (Abanda et al., 2017; Zhu et al., 2021) and assist with object recognition for on-site assembly (Dawod and Hanna, 2019). Layout information contained in the BIM is used to support robot indoor navigation tasks for building construction and maintenance (Follini et al., 2020; Park et al., 2016; Mantha et al., 2020). Commercial mobile robots have been introduced to draw layouts on-site based on BIMs (Dusty). The geometric information contained in BIMs has also been used to facilitate 3D printing in construction (Davtalab et al., 2018; Teizer et al., 2018).

BIMs can also provide information to support robot motion planning.




Fig. 2. Elements of the Updated System.

For example, in robotic brick assembly tasks, BIMs can provide position and orientation data for a robot to pick up and place materials, as well as task sequencing data to control the robotic workflow (Ding et al., 2020; McClymonds et al., 2022). IFC models have been adapted to work with robotic simulation platforms for robot navigation (Kim et al., 2021) and to simulate the robotic wall frame assembly process (Wong Chong et al., 2022). In these existing studies, robots fully rely on the BIM for task planning. The construction site needs to conform to the exact BIM specifications for the robot to perform construction work successfully. However, considerable uncertainties exist on construction sites. Deviated components, moving workers and equipment, and stacked materials on-site may interrupt the BIM-generated robot motions, causing robots to stall while performing construction work on-site. (Lundeen et al., 2019) used a combination of the BIM and sensing information to generate adaptive robot motions. Despite such advances, the robot's adaptability is limited to a narrow set of situations and construction tasks (Lundeen et al., 2019).

In summary, existing studies leveraging BIMs in robotics have three limitations. First, they lack generality to support various types of construction tasks. Second, they cannot handle uncertainties for field construction, which can go beyond the robot's adaptive capabilities and interrupt robot activities generated by the BIM. Thus, human intervention is necessary in addition to the BIM for the success of robotic field construction. Third, as-built data collected by the robot during the construction process is useful for the ensuing construction, operation, and maintenance phases of the project; however, a closed loop for a BIM to both provide and collect construction information is missing in existing studies. Therefore, a general framework that supports different types of construction tasks and allows human intervention is necessary.

2.3. Digital twins creation in robotic applications

Digital twins can be used for visualizing and incorporating information from different resources, and they also support real-time communication and interaction (Dembski et al., 2020; Wang et al., 2023). Therefore, they are a promising candidate to integrate BIMs with HRCC. Depending on the different application requirements, digital twins can be created with various approaches. One of the most popular methods in the AEC/FM industry is to use 3D point clouds. The environment is captured with laser scanners or depth cameras as 3D point clouds (Fang et al., 2016; Feng et al., 2015; Xu et al., 2019). Such systems can comprehensively capture the environment in real time, theoretically allowing for continuous updates of the digital twin to reflect the evolving environment at any point in time. However, the transmission of large-size point cloud data is computationally expensive and is subject to delays. Furthermore, subsequent steps of processing and registering the point clouds, object detection, or 3D reconstruction are usually needed to achieve the required functions (Zhou et al., 2020; Park and Cho,

(Kamat and Martinez, 2003) developed the VITASCOPE language to integrate simulation models, hardware control, and real-time construction data for dynamic construction scenario visualization at the operation level. (Liang et al., 2022) and (Roldán et al., 2019) created digital twins of a robot to program, control, and visualize robot motions. Joint state data are exchanged between the physical and virtual robots in real time. In order to reduce the computation load while allowing real-time visualization of the construction environment, (Wang et al., 2021) created a digital twin using a combination of a BIM, 3D meshes of as-built structures, and point clouds. However, these approaches require manually importing models or manually enabling the functionality of the digital twin. As a result, it interrupts the automated workflow of HRCC initiation, which can potentially hinder the widespread application of digital twins in HRCC. Therefore, an approach to automatically generate digital twins that are equipped with pertinent functions (e.g., target object selection, communication between modules) is necessary to promote and extend the autonomy of the HRCC workflow.

2.4. Research objectives

To address the abovementioned research gaps, a workflow with the following characteristics is needed to support HRCC effectively. First, instead of parsing specific information from BIM repositories to automate one type of construction work, a general framework that supports different types of tasks and components is needed. Second, the workflow should automatically interface with different construction tasks without additional programming or development effort that cannot be performed by construction workers without related expertise. Third, robots should have the ability to handle significant uncertainties on construction sites while allowing human intervention to resolve cases that extend beyond the robots' capabilities. Lastly, the workflow should record the construction-related data collected by the robot sensors during the HRCC process for future reference to enable loop closure. With these objectives, the following section presents a closed-loop generalizable framework integrating a BIM and HRCC, which supports automated collaborative workflows and can overcome uncertainties in field construction work.

3. Technical approach

A BIM-driven HRCC workflow enabled by closed-loop digital twins is proposed in this study. The BIM provides data (e.g., component geometry, position, type) to both the robot and the human co-workers by compiling and sending messages to ROS and Unity (where the interface is developed). The robot then generates the work plan based on the BIM and adapts the plan according to the as-built circumstances detected by its sensors. For example, during drywall installation, the robot retrieves the name and target position of the next panel to install from the BIM; it then adjusts the installation position of the panel based on how the wall frame has actually been built as detected by its camera. Next, human coworkers supervise the robotic construction process (e.g., by evaluating and approving the robot plan) and intervene to adjust the high-level task plan (e.g., by adjusting the target installation sequence and pose proposed by the robot) when necessary.

An overview of the BIM-driven HRCC process is shown in Fig. 3. First, the BIM data accessible by both human co-workers and robots needs to be created. Next, before construction starts, human workers need to prepare physically on the construction site (e.g., materials staging) and digitally in the BIM (e.g., task designation). Then, the interactive digital twin is generated, followed by the construction execution. Lastly, after certain construction tasks are finished, the BIM repository is updated with the latest as-built data. The remaining part of this section introduces the system design and the technical approach to enable this process.

3.1. System design

3.1.1. BIMs for robotic construction

BIMs created for traditional construction methods are typically incompatible with robotic construction (Meschini, 2016). Some additional elements are necessary for a BIM to better support human-robot collaborative task planning:

- Shop drawing-level geometry. Shop drawings precede detailed work plans and contain information needed for fabrication, assembly, and erection (Pietroforte, 1997). For example, in a robotic drywall installation task, shop drawings for drywall panels are needed so the robot knows where each panel should be located. However, shop drawing-level details are not needed for every component in BIM and are dependent on the construction plan. For example, an object that is prefabricated off-site or erected on-site as a whole can be represented in the BIM as one single component.
- Construction sequence. Detailed construction sequence information contained in the BIM is crucial to automate the construction process.

Fig. 3. BIM-driven HRCC Process.

The construction sequence information should be provided in correspondence with the shop drawing-level geometry, specifying the order of installation of components.

- Component relationships. Relationships between components can
 affect robot planning, especially when discrepancies exist and the
 robot needs to adapt its plan. Even though some component arrangements visually look the same, they might indicate different
 relationships (i.e., topologies) which require different construction
 plans. As a result, clearly defined component relationships in the BIM
 are necessary for the adaptive planning of the human-robot work
 team
- Component layers. A unified predefined layer structure in the BIM
 not only helps organize components into different groups for better
 user comprehension but also supports the development of interfaces
 that can quickly connect to different BIM projects, automating
 related processes in the project life cycle, such as construction.
 Therefore, a BIM layer structure is proposed to facilitate the automatic generation of interactive digital twins and the HRCC process,
 as shown in Table 1.
- Robot operation support. Adding information to support robot operation in the BIM can facilitate HRCC work. The information added depends on the task type and robot intelligence level. For example, robots can determine how to grip components by visually detecting component geometry in some cases, but for some components with irregular shapes, external guidance can increase the success rate of component gripping.

The creation and storage of these elements depend on the BIM platform selected. In this study, Rhino is used as the BIM platform (R. M.& Associates). The shop-drawing geometry, component name, and layer information are stored with the software's default field. Additional attribute data are stored as "Attribute User Text" in Rhino. For example, the component relationships are denoted by the "Parent" attribute of the components, while the sequence data are held in the "Sequence" attribute. To facilitate robot gripping, a Python script automatically calculates the gripping reference points from the component's vertices and

 Table 1

 BIM Layer Structure for Robotic Construction.

Layer Name	Description		
Target	Physical objects (e.g., timber) or virtual indicators (e.g., fastener locations) the robot needs to install or operate for the current		
A - D. 114	construction task.		
As-Built	Components that have already been built. If they are inside the workspace, they need to be considered for collision avoidance.		
	They update with the construction progress or as the robot senses		
	the environment.		
Materials	Construction materials staged on-site. If they are inside the workspace, they need to be considered for collision avoidance and may be updated during the construction process.		
As-Designed	The original design of the components. The information is used by		
110 2 00161100	human co-workers and robots to understand as-designed versus as-		
	built deviations and develop plans accordingly.		
Virtual	The space that is not physically occupied but the robot needs to		
Collision	avoid during the movement (e.g., a safety laser curtain that marks		
	the edge of the work zone). The robot considers it for collision		
	detection during motion planning.		

writes the data to the corresponding component attribute. This geometry, layer, and attribute data are extractable through scripts and can be communicated to ROS and Unity.

It should be noted that, although being manually created in this study, some of the abovementioned information has a high potential to be automatically generated by the computer or the robot. For example, (Kim et al., 2020) proposed an approach for automatically generating steel erection sequences and (Levine et al., 2018) used convolutional neural network and large-scale robot grasping experiments to generate robot grasping plans. (Adel et al., 2018) used computational design to generate the cutting planes, gripping planes, and connections for off-site frame prefabrication. This research focuses on how to leverage such information for HRCC; manual addition is thus sufficient for this study.

3.1.2. BIM-driven HRCC framework design

Five elements are included in the proposed framework for BIM-driven HRCC: 1) the BIM that provides and saves data about the construction project; 2) the Graphical User Interface (GUI) that supports both immersive VR and 3D options for human workers to interact with the robot; 3) ROS as the middleware for communication and the central unit for data processing, computing, and construction work process and physical robot control; 4) ROE, which is the construction site that includes robots, sensors, and materials; and 5) human workers who supervise the construction process and intervene when necessary. In this study, Rhino 7 is used as the BIM platform, and the GUI is developed in Unity with Oculus Rift S as the headset for the immersive VR option.

The information flow among system elements at different stages is shown in Fig. 4. To prepare for construction, setup activities are needed both physically on the construction site and digitally in the BIM. In general, workers need to start the sensors that are in use (e.g., cameras,




Fig. 4. System Information Flow at Different Stages.

LiDARs) on the robot or construction site for the robot to perceive the environment. They also need to place the required construction materials in the robot workspace for the robot to reach and manipulate. Lastly, workers need to assign tasks to the robot in the BIM (e.g., by selecting some drywall panels on the frame and placing them onto the "Target" layer). They should also adjust components' status in the BIM according to the task scope (e.g., marking components that are outside the robot workspace as "unrelated" by changing the user attribute data). Considering that a BIM interface is intuitive and generally familiar to construction personnel, it is typically easier for workers to indicate task scope in a BIM rather than directly indicate this to the robot in ROS.

When construction starts, information is taken from both the BIM and the construction site to generate the I2PL-DT. An automatic digital twin generation approach is proposed, which is introduced in Section 3.2.1. During the construction process, human co-workers collaborate with the robot through the digital twin system, which integrates information from the BIM and the construction site. The detailed approach to updating the digital twin and enabling HRC through bi-directional communication is discussed in Section 3.2.2. Section 3.2.3 introduces how the system addresses the challenges caused by component deviations on-site. The robot can suggest solutions to adapt to deviations to human co-workers for approval. Occasionally, human interventions (e. g., replacing a component with one of a different shape) are required to resolve the deviations.

When construction completes or reaches a certain checkpoint, the ROS environment that contains the related construction site information at the time sends the information to update the BIM repository and records data in the BIM for future reference. The technical approach to updating the BIM with construction data is introduced in Section 3.2.4. It must be noted that even though this study chooses to update the BIM at certain time points, the framework also allows the BIM repository to be continuously updated as construction progresses. Lastly, Section 3.2.5 explores the deployment of the physical system to collect and integrate data from the physical world and to control the physical industrial robot.

3.2. Technical approach for system implementation

3.2.1. Automatic digital twin generation

To initiate construction, it is essential to generate the digital twins

that integrate visualization, interaction, and computation functionalities. Our system incorporates two digital twins. One is the interaction module with the GUI developed in Unity, which facilitates visualization, supervision, and intervention. The other is the computation module within ROS that manages the construction workflow (e.g., installation sequence), adapts to as-built conditions, and generates task plans (e.g., collision-free motion plans). The generation of these digital twins takes advantage of the geometry and attribute data of components from the BIM. The coordinates of the digital twin world and the BIM are aligned using the robot's base frame as the origin point. Sensor data are also transformed into the robot base frame for integration into the digital twins. For example, for the camera sensor mounted on the robot in the experiments of this study, its pose relative to the robot link it is attached to is calculated through hand-eye calibration (Daniilidis, 1999). The relative pose is further transformed to the robot base frame using forward kinematics according to the current robot joint states. The automated generation process of the digital twin system is shown in Fig. 5.

The computation module is developed in ROS. Geometries of task-related components in the BIM are extracted as meshes, converted into ROS messages by a script in Rhino, and subsequently sent to ROS. Attribute information, including names, layers, and customized properties designated as Attribute User Text (discussed in Section 3.1.1), is also sent to the computation module in the form of ROS messages. Asbuilt data, including the locations of as-built components and materials, are loaded into the module when they are detected at the construction site. During the construction process, the system retrieves these data for task and motion planning. For example, the system queries the parent of the target and whether it is deviated to determine if adjustments are needed to install the target object.

Motion planning in the computation module is facilitated by the MoveIt planning framework (Chitta et al., 2012). The planning scene of the MoveIt framework contains a virtual robot model that replicates the actual robot using the URDF descriptions and synchronizes with the actual robot's states by subscribing to the joint_states topic. The planning scene also incorporates environmental representations, where meshes of task-related components on the "As-Built", "Materials", and "Virtual Collision" layers in the BIM are spawned at their corresponding locations as collision objects. The robot will use its camera to detect as-built components and construction materials in the workspace and subsequently update the collision information in the planning scene. If a




Fig. 5. Automatic Digital Twins Generation Process.

component has been constructed but its as-built model is not yet present in the BIM (not detected by the robot), its corresponding as-designed model will first be generated and later replaced by the as-built model once detected (e.g., through fiducial markers). Detected construction materials are similarly updated in the digital twin. These collision objects are used by the robot to plan collision-free paths during motion planning. When the robot arm holding a material, the corresponding collision object of that material is attached to the robot arm to ensure it is considered during motion planning.

The interactive digital twin module in Unity is generated by directly connecting Rhino and Unity through Rhino.Inside (Robert McNeel & Associates, Rhino.Inside, 2024), which is an open-source add-in that enables other applications (e.g., Unity) in the Windows Operating System (OS) to run Rhino and Grasshopper (a visual programming tool integrated with Rhino ([79]Grasshopper 3D, Wikipedia (2023). (https://en.wikipedia.org/w/index.php?title=Grasshopper_3D&oldid=1189175937) (Accessed 23 April 2024).)) projects. The highlight of this process is that

(Accessed 23 April 2024).)) projects. The highlight of this process is that instead of manually importing a BIM and creating functions in Unity for different construction projects, a Unity program template is developed. It contains template models with functions. When it receives information from other modules (e.g., a BIM), Unity can quickly generate interactive game objects using these template models according to the object layer. For example, when it receives an object assigned to the "Target" layer from a BIM, the program instantiates a game object with the target-type template. This game object is equipped with functionalities for user selection and pose manipulation. Meanwhile, the mesh geometry received from the BIM is loaded onto the game object for visualization, and the game object attributes such as name, layer, and material are set accordingly. As a result, the template Unity program can automatically generate interactive digital twin interfaces for different BIM projects.

At the initial state, Unity contains 1) light and camera systems for human partners to visualize objects in the game interface; 2) event systems to capture user input and enable interaction (e.g., selection, movement); 3) virtual robot models generated from the Unified Robot Description Format (URDF) files and meshes from ROS. One virtual robot is synchronized with the actual robot for supervision. The other virtual robot is used to evaluate robot motion plans and only appears when the human workers preview these plans; 4) ROS connectors to exchange data with ROS through Rosbridge using the ROS# library (Siemens, 2021); 5) a game object to run Rhino and Grasshopper projects to retrieve geometry and attribute (e.g., layer, name, type) data from the BIM; 6) model templates that can automatically generate interactive game objects with the information received; 7) interface templates containing text instructions and buttons that appear at specific times to prompt and receive user input; and 8) a virtual billboard to show messages.

As the system is initiated, Rhino and Grasshopper applications start with the Unity program through Rhino.Inside (Robert McNeel & Associates, Rhino.Inside, 2024). A script developed in Grasshopper then loads the BIM into Rhino, retrieves information (i.e., geometry, color, name, layer) of objects from the BIM, and sends it to Unity. As Unity receives the information, model templates can create game objects with the same names, colors, and geometry as what they received from the BIM. The generated game objects are automatically placed onto the corresponding layers in the GUI. Based on the object layer, scripts that contain different functions are embedded in the model templates and attached to the object, thereby creating different interaction patterns. At the same time, the communication between Unity and ROS is established through the Rosbridge WebSocket server (Crick et al., 2017), which enables the seamless interaction between the human co-worker and the robot during the construction process (Section 3.2.2). Lastly, the robot moves to scan materials and as-built components in the workspace. As-built components and materials detected are instantiated at their corresponding locations in Unity to provide the human co-worker with the most up-to-date representation of the construction environment. With these steps accomplished, the digital twin systems

are completely generated and construction can start.

3.2.2. Digital twin update for collaborative construction implementation

During the construction process, the seamless integration of the human co-worker and the robotic system is achieved through communications via Rosbridge (Crick et al., 2017), with ROS serving as the middleware. Data exchange occurs at various frequencies throughout the construction process. For example, joint states are written onto the physical robot at a fixed frequency of 250 Hz. In contrast, certain data are only published when specific events are triggered (e.g., the human co-worker makes a selection from the GUI). The HRCC process is shown in Fig. 6. Human operations and decisions are shown in orange, and blue elements show processes performed by the robot. The robot and its human co-workers interact through the GUI. The overall workflow is that the robot shows information and decisions intuitively in the GUI for its human co-workers to visualize. Then, the GUI detects the human co-workers' decisions and operations through their input and sends the information to the robot. During the interaction process, corresponding interfaces are generated from the interface templates to prompt the human co-workers on the current process and get inputs. The templates contain corresponding functions (e.g., sending messages to the robot on certain ROS topic channels when the user clicks certain buttons) and are automatically connected to corresponding scene objects when being

After generating the digital twins, the robot retrieves the next target in the construction sequence from the BIM and highlights the target object in the GUI in semi-transparent green. Meanwhile, it prompts the human co-worker to confirm the target by instantiating a UI in Unity with the natural language text "Want to install this?", where the coworker can respond by choosing either the "Yes" or "No" button. If "No" is selected, the human co-worker can select another target through mouse clicks on a computer or ray casting in VR. After a target is confirmed, the robot checks whether there are deviations in the workspace that affect the operation to achieve the target as originally designed (e.g., a deviated component occupying the target space will collide with the target if following the original design). If there is a deviation, the robot will propose suggestions to adapt (see Section 3.2.3 for the adaptation approach). Note that the adaptation decision is sometimes based on the robot's suggested solutions and sometimes based on human improvisations, thus the "adaptation" block appears in two colors. If no deviation exists, it will go ahead with the original installation pose from the BIM. The human co-worker can choose to directly accept the robot's suggestion (e.g., an adjusted pose to install the target). There might be situations where the robot cannot properly adapt, so the system also allows the human co-worker to improvise an adaptive plan (e.g., move the target to indicate a desired installation pose in GUI or directly install the component by themselves).

Next, based on the confirmed plan, the robot generates a collisionfree motion plan to achieve the target. When the human co-worker requests to preview the plan, a virtual robot will appear in the GUI and demonstrate the motion plan as an animation. The animation includes the robot movement during the whole manipulation process and the material movement if it is being held by and moving with the robot. This is enabled through a virtual joint state publisher in ROS that extracts and publishes the joint states in the generated motion plan at a given frequency. A virtual robot emulator in Unity subscribes to the topic that publishes the virtual joint states and moves according to the states received, thereby allowing the motion plan to be previewed as an animation. Such previewing processes enable the human co-worker to gain insights into the consequences of the robot operation and make better decisions (Kamat and Martinez, 2000). If the human co-worker is not satisfied with the motion plan, the robot will generate another plan with MoveIt and demonstrate it in the GUI until the human co-worker finds an acceptable plan. After a motion plan is accepted, the actual physical robot executes the approved plan. A detailed introduction of the processes to preview, execute, and supervise the robot motions can be found




Fig. 6. Collaborative Construction Process Flow Chart.

in the authors' previous work (Wang et al., 2021).

Since a robot model in GUI is synchronized with the actual robot by subscribing to its joint states, the human co-worker can supervise the robot execution states through this synchronized robot. They can also understand the robot's cognitive status (e.g., calculating the motion plan) through the virtual billboard in the GUI. It should be noted that certain steps of processing and robot operation can be skipped, depending on the type of human intervention. The technical approaches for establishing connections within the digital twin system and achieving motion planning, plan preview, and execution and supervision functions are discussed in (Wang et al., 2021). After a target is achieved, the system will check the next target in the sequence from the BIM and go through the process again. If no target is left in the queue, the assigned task is considered to be finished.

3.2.3. Deviation adaptation

This study develops methods to enable robots to provide suggestions for adapting to two types of deviations commonly found in construction assembly tasks. The process is supervised by the robot's human co-

worker, and if needed, the human can intervene to adjust the robot's suggested solution or improvise a different adaptation strategy.

3.2.3.1. Parent deviation. The parent of the target to be installed is built with deviations from its design. Since the target needs to be connected to its parent, the installation pose of the target should be adjusted accordingly. Two sources of transformation information are used to address the deviation. The robot receives the as-designed position and orientation of the parent object from the BIM through Rosbridge at the beginning of the construction, which is then converted into a transformation matrix T_D . The as-built transformation of the parent object T_B is detected by the robot with the camera. After both transformations are received, the robot first calculates the design-built deviation T_D^B of the parent using $T_D^B = T_B T_D^{-1}$. Next, it calculates the suggested transformation matrix T_t to install a target t using $T_t = T_D^B D_t$, where D_t is the as-designed transformation of the target coming from BIM. Lastly, the installation transformation matrix T_t is converted into an installation pose P_t with position and orientation information for robot

planning and operation.

3.2.3.2. Nearby object deviation. When certain objects near the target are built with deviation, they might occupy the originally planned space of the target. Before installation, the robot checks whether the planned installation place collides with any as-built objects. This process is enabled by the collider functions in Unity. If no collision is detected, the robot will plan to go ahead with the original plan by default. Otherwise, the robot will provide suggestions to offset the target installation pose to avoid collision based on the deviation of the object that conflicts with the target object.

3.2.3.3. Human supervision and intervention. The robot's suggested solution always requires human approval before execution to prioritize human preferences. The suggested installation pose is communicated to human co-workers by instantiating a new object with the same geometry as the target object highlighted in semi-transparent red material in the digital twin interface. Meanwhile, an interface template is instantiated asking "Robot suggest install it here. Do you accept?". The human can choose to take the robot's suggested solution by clicking on the "Yes" button. However, due to the possible uncertainties and complexities of construction work, the deviation type may not belong to the two situations considered above or the solution suggested by the robot may not be optimal, especially for the nearby object deviation case where situations vary. For example, offsetting one component may affect the installation of subsequent targets, causing construction plan changes for several targets. In this case, the human co-worker may prefer to manually replace the target with one in a different shape (e.g., a smaller piece). Even if the deviation does not introduce collisions (object deviates towards other sides), the human co-worker may still want to adjust the target workpiece to make it stay together with the objects nearby. In these cases, the human co-worker will reject the robot's suggested solution and manually intervene.

The system affords two operations to facilitate human intervention. First, they can manually adjust the position and orientation of the target installation pose through sliders in the interface. Otherwise, they can skip the robotic installation in the digital twin and manually adjust and install the target. In this case, they need to manually record the information in the BIM to make it available for future use.

3.2.4. BIM information update

When an assigned construction task finishes or reaches a certain checkpoint, three sources of data tracked by ROS can be sent to the BIM via Rosbridge using the COMPAS library (COMPAS, COMPAS, 2021). Three sources of data are saved in the BIM repository for future reference. The workspace sensing data as the robot scans the environment and the robotic construction data reflected by robot states are saved onto the "As-Built" layer. The temporary material data (i.e., on-site construction material type, number, and locations) are saved onto the "Materials" layer. It is inferred from the start state (e.g., materials originally prepared) and the construction process (e.g., how many materials are used).

To update the BIM, the pose and type (applies to Materials only) data of these components in the ROS computation module are sent to the BIM. Then, new components are instantiated in the BIM at the given poses, with their geometries retrieved from corresponding components previously existing on the other layers in the BIM. The Python script in Rhino assigns names and layers to the instantiated components and generates customized attribute data (e.g., component poses) as Attribute User Text. Meanwhile, the components on the "Target" layer that are installed by the robot are switched to the "As-Designed" layer. In the ensuing steps, the repository will continue updating itself with incoming sensing data and completed construction work.

3.2.5. Physical system deployment

The physical portion of the system is deployed on a large-scale Kuka industrial robotic arm in a research laboratory setting designed to mimic a construction site. The industrial robotic arm is selected because it has a relatively large payload to manipulate heavy construction components and higher flexibility to perform various construction tasks with different end effectors. The assumption is that the robot has a relatively static workspace (e.g., an area in a room) for each construction task. Other workers and equipment conduct construction activities and move outside the robot workspace. For safety reasons, if they get into the robot workspace during the robotic construction process, the robot will stop moving until safety is confirmed by its human co-worker.

The system involves several devices connected to a Local Area Network (LAN). Devices can communicate with each other through wired connections or wirelessly. The device communication and robot control processes are shown in Fig. 7. The interfaces that the human coworker directly uses, including the GUI in Unity and the BIM in Rhino, need to run on a computer with Windows OS. The sensors are connected to portable microcontrollers (e.g., Raspberry Pi). Both the Windows computer and microcontrollers can communicate with ROS wirelessly through a router on the LAN via ROS messages. ROS runs on a computer with Ubuntu OS that is connected to the robot embedded PC through an Ethernet cable. The computing core in ROS sends the joint states to the Automation Device Specification (ADS) interface of the programmable logic controller (PLC) (Liang et al., 2022). ADS is an interface layer of Twincat PLC that allows commands and data exchange between different software modules (Beckoff, 2022). The joint states data is received by the PLC and is then sent to the Kuka Robot Sensor Interface (RSI) to control the robot (Liang et al., 2022).

4. System verification and case study

In order to verify the proposed system and explore the setup necessary for its physical deployment, a drywall installation case study is conducted in a research laboratory, which is set up to mimic a construction site, as a proof-of-concept implementation. Drywall installation is one of the most prevalent construction activities. It is also a representative example of large-scale object manipulation and pick-andplace operation, which is a common scenario in construction and comprises the elemental motions for a variety of construction tasks on structures (e.g., framing), surface (e.g., ceiling tile installation), and systems (e.g., ductwork installation) (Park et al., 2024; Feng, 2015). In this context, the wall frame itself is prefabricated without deviation but is purposefully installed at a deviated pose on-site to simulate the case of parent deviation. Four drywall panels in two different shapes need to be installed onto the wall frame, simulating scenarios such as windows, doors, or room corners that require varied panel sizes beyond the standard dimensions. The remaining part of this section introduces the physical and software setup and describes the HRCC process to perform the drywall installation task in detail.

4.1. Physical setup

The robot used for the case study is a 6 DOF Kuka KR120 industrial robotic arm that has a 120 kg payload and a 2.7 m reaching range. By mounting it onto Kuka KL4000 Linear Unit, its base can move 4.5 m linearly, which adds one DOF to the robot and significantly increases the robot's physical reach. Therefore, the robot has the capability to manipulate a regular-sized drywall panel. The robot workspace is shown in Fig. 8. A safety gate is used to mark the robot workspace and a laser curtain is installed on the safety gate to prevent other workers and equipment from entering the robot workspace while the robot is operating.

Since the goal of the case study is to verify the capability of the system framework and functions, the experiment is conducted on a 1:2 scale. A wall frame 4 feet (1.2192 m) tall by 8 feet (2.2384 m) long with




Fig. 7. Physical Robot System Framework.




Fig. 8. Robot Workspace.

a window area is built with studs on the back side to ensure stability (Fig. 9). To expand the workspace, part of the frame support is placed outside the gate, but it does not break the operation because it is lower than the bottom of the curtain. The robot needs to install three larger drywall panels of 2 feet (0.6096 m) by 4 feet (1.2192 m) and one smaller panel of 2 feet (0.6096 m) by 2 feet (0.6096 m) onto the frame. A cubic handle is attached to each panel for the robot to grip. A pneumatic




Fig. 9. Wall Frame and Drywall Panels Used in Case Study.

gripper is designed and connected to the robot with a tool changer and a connection plate (Fig. 10). The jaws of the gripper are made with slopes to clutch the cubic handle on the drywall panel. Stabilizers are installed to ensure that the drywall panel can fully contact the gripper to avoid torque and shaking during manipulation. Rubber pads are used to add friction between the gripper and the cubic handle to prevent slippage.

Given that only one robotic arm is deployed, for demonstration and experiment repeatability, Medium-Density Fiber (MDF) boards with higher durability are used as drywalls. Magnets are used to attach the panels to the wall frame after the robot releases the panels. For actual construction work, the panels could be fixed (typically with screws) onto the wall frame, potentially by a human worker or another robot. An RGB camera is fixed onto the gripper. It is connected to ROS running on a Raspberry Pi microcontroller powered by a portable battery. Raspberry Pi can send the camera sensing data as ROS messages wirelessly to the ROS master running on the Linux machine. AprilTag fiducial markers are positioned near the wall frame and on the panels, and can be localized with the RGB camera (Krogius et al., 2019). The markers store information about the component type and the offset from the marker to the component's origin to help identify the components and their 6DOF pose. The type and offset information can be easily modified by updating the configuration file to accommodate multiple tasks.

4.2. Preparation of the BIM

Fig. 11 shows a screenshot of the BIM used for the drywall installation task. The surrounding wall of the laboratory is set to be transparent grey to make it easier to visualize the robot workspace. Shop drawings for drywall installation are shown at the right bottom of the figure. The BIM indicates how the panels are designed to be installed. In this drywall installation task, these panels are specified as targets. The laser curtain is the plane that lasers come through which does not physically exist.




Fig. 10. Gripper Design.




Fig. 11. The BIM for Drywall Installation.

However, interruption of the laser will cause the robot to stop for safety reasons, so the robot should not get into the curtain during operation. Thus, the laser curtain is considered a collision object during robot motion planning. The BIM components and their corresponding layers are shown in Table 2. Before construction, the frame has already been installed and materials are prepared but their poses are unknown and need to be detected by the robot.

The BIM contains the component attributes needed for robot processing and construction, such as its identifier, layer, its relationship with other components, whether it is related to the current task, construction sequence, and type (e.g., large or small) (Fig. 12). For manipulable components, how the robot should grip the component is also indicated (e.g., at its center with orientation perpendicular to its largest surface), which is also used as the indicator of robot picking and installation pose. In this study, the program automatically calculates pose indicators using the centroid of the Rhino object. Otherwise, pose indicators can be automatically generated with computational design or manually specified by human workers selecting points and directions in Rhino.

4.3. Construction process

To prepare for the construction work, the drywall panels are placed into two stacks in the robot workspace (Fig. 9). There is a marker on each panel and the wall frame. Offsets from the markers to the objects' pose indicator points are recorded and input into the system. The marker is used not only for pose estimation but also to provide configurable attribute information (e.g., corresponding object type and quantity).

As construction starts, the robot follows a predefined trajectory to scan the environment. After scanning, the robot replaces the as-designed wall frame with the as-built one in the MoveIt planning scene. In the meantime, material poses are inferred from the detected stack location, quantity, and type data attached to the marker. The materials are also added to the MoveIt planning scene as collision objects. When the robot plans motion with materials in hand, the collision object of the corresponding material is attached to the robot end-effector to ensure that the material held by the robot does not collide with the environment or the robot itself. The as-built wall frame and materials are also sent to Unity to be generated in GUI to support user visualization and decision making.

Table 2The BIM Components List.

Components	Layers
Workspace surroundings (Blue)	As-Built
Frame (Design) (Yellow)	As-Designed
Target panels on frame (Design)	Target
Laboratory walls, breams, and columns	As-Built
Laser curtain (Virtual)	Virtual Collision




Fig. 12. Attribute Information in the BIM to Drive Robotic Construction.

The robot first highlights the next drywall target in the construction sequence in the GUI and asks for the human co-worker's confirmation or adjustment (Fig. 13a). After the human co-worker confirms the target, the robot uses the as-built and as-designed deviation of the wall frame to calculate a suggested drywall installation pose. Visualization of the suggested pose is then generated in GUI for the human co-worker's approval or adjustment (Fig. 13b). In both VR and 3D modes, human co-workers can adjust the camera view to inspect the environment from the perspectives they prefer, while VR offers a more natural and intuitive sight of view control. A video demonstrating the adjustment process is shown in Video 1.

After the installation pose is approved, the robot generates the motion plan to first pick up a corresponding type of panel (i.e., large or small) from the detected panel stacks and then places it with the approved installation pose onto the wall frame. Upon request from the human co-worker, a virtual "planning" robot manifests in the GUI and demonstrates the robot motion plan and how the panel is manipulated during the installation process for evaluation (Fig. 13c). If the motion plan is approved, the physical robot executes the plan, and the human co-worker can supervise the robot execution process with the synchronized robot and understand the robot status from the messages in the GUI (Fig. 13d). After the robot releases the panel, the panel is attached to the wall frame with magnets, and the virtual panel in Unity is changed to the "As-built" layer.

The actual installation pose is recorded by the robot and the robot prompts the next panel in the sequence for installation. The quantity of materials in the corresponding panel stack is reduced by one, and the position for the robot to reach the next piece of panel in that stack is updated accordingly. These procedures are repeated until all four pieces of drywall panels are installed. The snapshots of the physical robot drywall installation process during the laboratory experiment are shown in Fig. 14. A video demonstrating the process is uploaded as Video 2. After referring to the ISO 12018–1:2011 ISO (n.d.) and the robot manual, the reviewer found 3% of the robot full speed, which set the maximum Tool Center Point (TCP) speed at 60 mm/s (below the specified threshold of 250 mm/s of robot part replacement and reduced speed control), as a comfortable operation speed for the research team to manage and respond to emergencies, minimizing the risk of accidents and preventing potential damage to the laboratory and the robot.

After all the panels are installed, the as-built condition of the wall frame is sent from ROS to Rhino through Rosbridge using COMPAS as the workspace sensing data (COMPAS, COMPAS, 2021). The recorded installation poses of all panels are inferred from the robot end-effector pose and are also sent to be saved in the BIM as the robotic construction data. Both the workspace sensing data and the robotic construction data are saved onto the "As-Built" layer. Lastly, the up-to-date conditions of the panel stacks are sent to Rhino and saved onto the "Material"





Fig. 13. Screenshots of the HRCC Process.



Video 1. User_Adjustment.A video clip is available online. Supplementary material related to this article can be found online at doi:10.1016/j.compind.2024. 104112.

layer to reflect the quantity and location of the remaining panels on-site. The updated scene in the BIM is shown in Fig. 15.

5. System validation experiments

5.1. Physical experiments for overall system evaluation

In Section 4, a drywall installation case study on the physical robot is used to verify the proposed workflow. It is a representative activity in construction to demonstrate the workflow. However, the specific nature of the task does not allow for the exploration of error margins by varying spacing through repeated experiments to evaluate system performance. As a result, block pick-and-place experiments that involve a line of four

blocks are conducted to validate the system's performance. The BIM repository of the system and the physical experiment setting are shown in Fig. 16. Four wood blocks are stacked on the ground floor. A stud is used to represent a nearby object, possibly installed in earlier construction states. AprilTag markers are positioned near the block stack and the stud for component identification and localization. The blocks are expected to be placed in a line adjacent to the stud. Block pick-and-place is selected as the task here because it is fundamental yet representative of construction activities. On one hand, its simplicity facilitates repetitive testing and control over experimental conditions, such as the spacing between blocks and end stud positioning. On the other hand, it requires precision and adaptability to deviations typically needed for construction tasks thereby allowing us to evaluate system performance




Fig. 14. Snapshots of Physical Robot Drywall Installation Process.

in a representative construction context.

The robot first scans the environment to localize the block stack and stud through the ApirlTag markers placed near these components. Then, it needs to first pick up a wood block from the stack of blocks and place it alongside the stud placed on the ground. If the robot finds the stud takes up the space for the planned block placement target, it will suggest offsetting the block placement target to avoid collisions. If the stud does not occupy the space of the blocks, the robot will follow the original plan and will not automatically make adjustments, unless instructed by the human supervisor.

In order to increase system tolerance to errors and prevent damage to experiment materials and the robot, gaps of different sizes (10 mm, 5 mm, 3 mm, and 1 mm) are left between blocks. The gap sizes are initiated at 10 mm and are gradually reduced to approximately half of the previous value to test the margin of system precision. The gripper releases and drops the block 2 mm above the ground floor, leaving room for possible vertical errors. For each gap size, 10 trials of picking and placing all four blocks were carried out. The wood stud was deliberately placed in collision with the planned target for 5 out of the 10 trials to test

the robot's capability to resolve deviation. Since the task has lower risks compared to drywall installation, the robot is operating at a slightly higher speed of 7% of the robot's full speed (140 mm/s) as the research team's comfortable speed for experiment management and emergency handling.

During the experiment, the human co-worker interacts with the robot through the 3D interface. The goal of this experiment is to verify the overall performance of the proposed system when the human workers completely rely on robot suggestions. Therefore, the human co-worker agrees with all robot suggestions and does not perform any adjustment or manual intervention during the construction process. However, when the co-worker feels the robot planned manipulation trajectory is not optimal (e.g., taking extra rotations), the co-worker would request the robot to generate a new motion plan for evaluation. The number of replanning requests from the human co-worker is recorded. The trial is counted as a failure if the robot does not place all four blocks successfully.

The success rate and the number of replanning requests for different gap sizes are shown in Table 3. "Successful placements" means the

Physical environment

Digital twin GUI



4x

Video 2. Construction_Process.A video clip is available online. Supplementary material related to this article can be found online at doi:10.1016/j.compind.2024.





Fig. 15. The Updated BIM.

number of blocks successfully placed by the robot without any collision. Once a block fails, the trial ends and the rest of the blocks in the four-block line are not placed, resulting in more than one block not being



(a) BIM at Experiment Start

(b) BIM at Experiment Finish



(c) Experiment Start (Physical)

(d) Experiment Finish (Physical)

Fig. 16. Experimental Settings.

Table 3Block Pick-and-Place Experiment Results.


Size of gap	Success rate (%)	Replan requests / Successful placements	Reason for failure (occurrence)
10 mm	100	7 / 40	
5 mm	90	2/38	Hit ground (1)
3 mm	90	6 / 36	Collide with stud (1)
1 mm	60	5 / 26	Collide with stud (3) Hit ground (1)

successfully placed with one failure case. For example, failure of the first block placement will end the trial and cause all four blocks not being successfully placed. On average, a successful pick-and-placement trial of four blocks takes 217.31 seconds. 56.38 seconds are used for human coworker's decision-making, such as confirming the target and previewing the motion plan. The average time taken by robot computation and execution is 160.93 seconds.

5.2. Simulation experiments for validation of nearby object deviation adaptation

In order to specifically assess the system's capability to autonomously adapt to deviations of nearby objects and to accurately trace source errors in physical experiments, a block pick-and-place experiment is conducted in Gazebo simulation, mirroring the settings of the experiments in Section 5.1. While physical experiments evaluate the performance of the overall system, simulation enables precise tracking of component positions and orientations for performance assessment and allows isolating other error sources to focus on the evaluation of specific system components. It should be noted that the Gazebo simulation has been demonstrated to be replicable on the physical robot system used in this study with high accuracy (Liang et al., 2022). In this experiment, the robot is provided with ground truth poses of tags to eliminate errors arising from component localization. The stud is intentionally offset towards the target block placement location, necessitating robot adaptation to avoid collisions. Across 10 trials, the deviation distance of the stud is set to a randomly generated value between 0 and 0.2 m. No gaps are left between blocks or between a block and the ground. As the focus is to evaluate the robot's capability for autonomous deviation adaptation, all the robot's suggested solutions are accepted without human intervention.

Ground truth poses and actual locations of each of the four blocks in



(b) Digital twin interface (yellow: as-designed; red: as-built)

Fig. 17. Examples of Block Pick-and-Place Simulation Experiments.

Table 4Error Analysis for Block Pick-and-Place Simulation Experiment.


	Position errors			Orientation errors		
	x	у	z	roll	pitch	yaw
RMSE	1.657e-	5.163e-	4.864e-	2.033e-	1.289e-	2.426e-
	04	05	04	04	04	04
STD	1.651e-	5.023e-	4.534e-	1.939e-	1.266e-	2.423e-
	04	05	04	04	04	04

the simulation environment are recorded and compared. To avoid errors due to movements of the loose objects post-handling, actual block locations are recorded before the robot releases them. Fig. 17 shows examples of the experiment results. The stud is in white and the blocks are in wood material in Gazebo simulation. Deviations of the stud and the adapted installation pose can be visualized in the digital twin interface. Errors of all blocks across 10 trials are analyzed in Table 4. Both the Root Mean Square Error (RMSE) and the Standard Deviation (STD) are close to zero, demonstrating the effectiveness of the proposed deviation adaptation method for the nearby object deviation situations.

5.3. Simulation experiments for validation of parent deviation

To assess the system's capability to autonomously adapt to the parent deviations, a drywall installation experiment with settings replicating the case study in Section 4 is conducted in Gazebo simulation. Ground truths of tag poses are provided to the robot to eliminate the errors arising from component localization. The frame is intentionally offset in both position and orientation to necessitate the adjustment for subsequent installation of panels. Across 10 trials, the deviation distances of the frame on the X and Y axis are set to randomly generated values between 0 and 0.2 m. The yaw orientation deviation of the frame is randomly generated between 0 and 15 degrees. This range ensures the frame stays within the robot workspace and the panel installation pose are valid and reachable by the robot. The robot's suggested solutions are always approved without human intervention.

The experiment compares the actual poses of each of the four panels in the simulation environment with their ground truth poses. Fig. 18 shows examples from the experiment trials. The deviations of the frame, along with the original and adapted installation pose, can be visualized in the digital twin interface. The errors of all panels across 10 trials are



(b) Digital twin interface (yellow: as-designed; semi-transparent: original targets; red: as-built)

Fig. 18. Examples of Drywall Installation Simulation Experiments.

Table 5Error Analysis for Drywall Installation Simulation Experiment.

	Position errors			Orientation errors		
	x	у	z	roll	pitch	yaw
RMSE	8.347e-	8.513e-	1.160e-	6.046e-	3.759e-	1.376e-
	04	05	04	05	05	05
STD	8.211e-	8.311e-	6.481e-	3.340e-	2.268e-	1.288e-
	04	05	05	05	05	05

analyzed in Table 5. Similar to the nearby object deviation situation, both the RMSE and the STD are close to zero, demonstrating the effectiveness of the proposed deviation adaptation method for the parent deviation scenarios.

6. Discussion

In order to successfully perform the construction work with the proposed system, the robot needs to adequately localize components in the construction environment, make decisions and suggestions to adapt to uncertainties, and accurately reach specific positions and manipulate components. Errors in any of these aspects will disrupt the workflow. The low errors from experiments in simulation indicate that the robot can accurately make adaptations and find the appropriate pose to place the target. The block pick-and-place experiment with a physical robot is conducted to evaluate the overall system performance. It is observed that once the first block is placed, the rest of the blocks are placed without collision with each other. It indicates that after the robot accurately determines the adapted installation poses, it executes the plan with high precision.

Most failure cases are caused by the first block colliding with the stud while being placed (Fig. 19). There are also two cases of failure where the blocks were moved too close to the ground and the robot sensed excessive force on its end-effector. These failures are caused by errors in component localization. AprilTag markers are used for component localization, which is a low-cost and easy-to-deploy solution that provides relatively high localization accuracy and is robust to various environmental conditions (Lundeen et al., 2016; Feng and Kamat, 2013). However, it still introduces certain localization errors, which can lead to collisions when the tolerance is very low. For example, in the drywall installation case study, the panel cannot be firmly held onto the frame if a minor gap between magnets exists. Since the marker is installed on one end of the frame, orientation errors in marker detection are amplified by the long distance and cause a larger position offset when installing the panel on the other end of the frame. This results in task failure in some cases during the implementation process.




Fig. 19. Collision with Stud during Block Placement.

Fortunately, with the evolving object detection algorithms and hardware (e.g., LiDAR) (Du et al., 2021; Fan et al., 2022), the accuracy of component localization is increasing to meet the needs of precise construction tasks.

Considering the visual localization error, the success rate of the block pick-and-place experiment is found to be particularly high. Several reasons may lead to this result. First, all the blocks are stacked at one location, and thus the same offsets are maintained for all blocks. Therefore, collisions between blocks are avoided provided that the digital twin system successfully adapts to the nearby object deviation. Second, the gripper compensates for certain localization errors when closing the jaws to grab the block at its horizontal center. Third, only the localization error in a certain direction can cause task failure. For example, the block will only collide with the stud if the stud is in the way of the block target pose but the robot thinks the stud is still far away and does not make any adjustments to avoid the collision. Fourth, the robot drops the blocks onto the ground at a height of 2 mm, which increases the vertical tolerance of the task. Even if the robot drops the block from a slightly higher or lower position, the block placement is still considered successful.

This study leverages the meshes as BIM component geometry and employs the proposed layer structure to generate the interactive digital twin through template programs in Unity, demonstrating that the digital twin can be generated provided the components are placed on the designated layers. Different from existing studies that parse component IFC files for robot motion planning, this study directly loads the meshes of BIM components as collision objects in the MoveIt planning scene and uses the attribute data from the BIM to generate collision-free motion plans. Therefore, the manipulation targets or other objects are not required to conform any specific shape or follow a particular IFC structure to be processed by the system. The BIM update process leverages the existing component geometries in BIM and generates asbuilt data by offsetting the existing components based on the subscribed pose information. This approach avoids the challenges associated with creating diverse and complex geometries. These features enhance the framework's flexibility for various types of construction assembly tasks. Two distinct tasks, drywall installation and brick pickand-place, are implemented in this study for verification. Since a variety of other construction tasks can be similarly composed with the underlying elemental motions and large-size object manipulation methods demonstrated in these example tasks, the developed methods can be readily adapted to new tasks directly or with minor modifications (Park et al., 2024; Feng, 2015). However, it should be noted that the proposed system is primarily designed for rigid objects and is less effective for tasks involving fluid or deformable materials such as freshly mixed concrete or waterproofing membranes.

During the physical experiment, several limitations are observed, and future research directions are identified. First, as discussed above, although the robot can localize objects with up to millimeter-level accuracy, it is not sufficient for some construction tasks that require high precision. It also takes time to set up and for the robot to scan fiducial markers on all related components in the workspace. A more direct and precise approach for the robot to perceive the environment, continually track components, and subsequently update BIM based on the detected installation pose of components should be considered in future developments.

Second, because of the laboratory condition, only one robotic arm is used, and the panels are grabbed by a 2-jaw gripper in the drywall installation case study. One more robotic arm can be included to fasten panels onto the wall frame, and a vacuum gripper can be used to grab panels so that cubic handles are not needed.

Third, information to support robotic construction, such as robot gripping pose and construction sequence, is manually created in the BIM. Future work should integrate computational design into the system, which can automatically generate detailed digital fabrication information, construction sequence, and gripping plans for components

(Adel, 2020).

Fourth, some motion plans generated by the robot are valid but not desirable, and replanning is preferred. Sometimes, the robot manipulates material extremely close to other objects on-site. While no collision occurs, these situations cause high mental stress on human co-workers when the workpiece is large. Future studies may consider applying force feedback control and reinforcement learning for more trustworthy and desirable component manipulation (Emaminejad and Akhavian, 2022; Liang et al., 2022).

Lastly, for experimental purposes, the robot's working speed is deliberately set to a slow pace (3% or 7% of its full capacity) to minimize risks such as object falls, collisions, and robot damage, and to emphasize the safety of the research team conducting the experiments. This results in extended work times. In the future, the efficiency of the workflow can be improved by applying faster robot speed, foregoing the preview step for low-risk operations, and eliminating the need for human approval when the confidence level of robot decision is high. Future studies will benefit from a comprehensive efficiency assessment that analyzes various impact factors.

7. Conclusions

This study proposes a BIM-driven HRCC workflow that addresses technical solutions ranging from the preparation stage to the end of the construction work, enabled by a closed-loop digital twin framework. The proposed framework offers several significant improvements to the previous I2PL-DT as well as other independent contributions. First, it presents a BIM framework that supports HRCC. The BIM contains the attribute and geometric information human workers and robots need for construction, and the predefined layer structure provides a unified standard to interface different BIM projects with the interactive digital twin, thereby improving BIM interoperability. Second, an automatic approach for generating interactive digital twins for HRCC is proposed, which is enabled by a template-based Unity program and the predefined layer structure in the BIM. Third, this study introduces an approach for component placement deviation adaptation using a combination of asdesigned data from the BIM and perceived as-built information. Lastly, the construction site as-built information is sent to the BIM for recording, forming a closed-loop system. By closing the loop, the BIM is updated with as-built data to support decision-making and automation in subsequent construction, operation, and maintenance of a facility.

Physical and simulation experiments are conducted to identify the effort needed to enable a physical construction robotic system, verify and validate system performance, and recognize limitations for future improvements. Overall, through the integration of the BIM, the proposed system not only improves construction work quality but also increases the robot's capability in lower-level task planning thereby reducing human workers' planning efforts.

CRediT authorship contribution statement

Vineet R Kamat: Writing – review & editing, Visualization, Validation, Supervision, Resources, Project administration, Methodology, Investigation, Funding acquisition, Formal analysis, Conceptualization.

Wes McGee: Writing – review & editing, Validation, Supervision, Software, Resources, Methodology, Investigation, Data curation. Carol C Menassa: Writing – review & editing, Visualization, Validation, Supervision, Resources, Project administration, Methodology, Investigation, Funding acquisition, Formal analysis, Conceptualization. Xi Wang: Writing – original draft, Visualization, Validation, Software, Methodology, Investigation, Formal analysis, Data curation, Conceptualization. Hongrui Yu: Writing – review & editing, Visualization, Validation, Software, Methodology, Investigation, Formal analysis, Data curation, Conceptualization.

Declaration of Competing Interest

The authors declare the following financial interests/personal relationships which may be considered as potential competing interests: Carol C. Menassa reports financial support was provided by National Science Foundation. If there are other authors, they declare that they have no known competing financial interests or personal relationships that could have appeared to influence the work reported in this paper.

Data availability

Data will be made available on request.

Acknowledgments

The authors would like to acknowledge the financial support for this research received from the U.S. National Science Foundation (NSF FW-HTF-P #2025805 and FW-HTF-R #2128623). Any opinions and findings in this paper are those of the authors and do not necessarily represent those of the NSF.

References

- Abanda, F.H., Tah, J.H.M., Cheung, F.K.T., 2017. BIM in off-site manufacturing for buildings. J. Build. Eng. 14, 89–102. https://doi.org/10.1016/j.jobe.2017.10.002.
- Adami, P., Rodrigues, P.B., Woods, P.J., Becerik-Gerber, B., Soibelman, L., Copur-Gencturk, Y., Lucas, G., 2021. Effectiveness of VR-based training on improving construction workers' knowledge, skills, and safety behavior in robotic teleoperation. Adv. Eng. Inform. 50, 101431 https://doi.org/10.1016/j.aei.2021.101431.
- A. Adel, Computational Design for Cooperative Robotic Assembly of Nonstandard Timber Frame Buildings, Doctoral Thesis, ETH Zurich, 2020. (https://doi.org/10.3929/eth z-b-000439443).
- A. Adel, A. Thoma, M. Helmreich, F. Gramazio, M. Kohler, Design of Robotically Fabricated Timber Frame Structures, in: Mexico City, Mexico, 2018: pp. 394–403. (https://doi.org/10.52842/conf.acadia.2018.394).
- AGC, 2022. Construction Outlook National Survey Results, 2022. Associated General Contractors of America. (https://www.agc.org/sites/default/files/users/user2 1902/2022_Outlook_National_0.pdf) (Accessed 31 August 2023).
- R. Aulin, M. Jingmond, Issues confronting women participation in the construction industry, in: Makere University, Uganda, 2011: pp. 312–318. (http://lup.lub.lu.se/ record/1834659) (Accessed 31 August 2023).
- Barbash, Gabriel I., Glied, Sherry A., 2010. New technology and health care costs the case of robot-assisted surgery. N. Engl. J. Med. 363, 701–704. https://doi.org/ 10.1056/NEJMp1006602.
- Beckoff, Beckoff Information System ADS Introduction, (2022). (https://infosys.beckh off.com/english.php?content=./content/1033/tcadscommon/html/tcadscommon intro htm%id\=
- Brosque, C., Hawkins, J.T., Dong, T., Örn, J., Fischer, M., 2023. Comparison of on-site and off-site robot solutions to the traditional framing and drywall installation tasks. Constr. Robot 7, 19–39. https://doi.org/10.1007/s41693-023-00093-8.
- Cai, J., Du, A., Liang, X., Li, S., 2023. Prediction-based path planning for safe and efficient human–robot collaboration in construction via deep reinforcement learning. J. Comput. Civ. Eng. 37, 04022046 https://doi.org/10.1061/(ASCE) CP.1943-5487.0001056.
- Chitta, S., Sucan, I., Cousins, S., 2012. Movelt! [ROS Topics]. IEEE Robot. Autom. Mag. 19, 18–19. https://doi.org/10.1109/MRA.2011.2181749.
- Chotiprayanakul, P., Liu, D.K., Dissanayake, G., 2012. Human–robot–environment interaction interface for robotic grit-blasting of complex steel bridges. Autom. Constr. 27, 11–23. https://doi.org/10.1016/j.autcon.2012.04.014.
- COMPAS, COMPAS, (2021). (https://compas.dev/).
- F. Correa, Robot-Oriented Design for Production in the context of Building Information Modeling, in: Auburn, AL, USA, 2016. (https://doi.org/10.22260/ISARC2016/010 3).
- Correa, F., 2019. Simulating Wood-framing Wall Panel's Production with Timed Coloured Petri Nets. in: ISARC. Proceedings of the International Symposium on Automation and Robotics in Construction. IAARC Publications, Waterloo, Canada, pp. 1026–1033. https://doi.org/10.22260/ISARC2019/0137.
- Crick, C., Jay, G., Osentoski, S., Pitzer, B., Jenkins, O.C., 2017. Rosbridge: ROS for Non-ROS Users. In: Christensen, H.I., Khatib, O. (Eds.), Robotics Research: The 15th International Symposium ISRR. Springer International Publishing, Cham, pp. 493–504. https://doi.org/10.1007/978-3-319-29363-9 28.
- Daniilidis, K., 1999. Hand-eye calibration using dual quaternions. Int. J. Robot. Res. 18, 286–298. https://doi.org/10.1177/02783649922066213.
- Davids, A., 2002. Urban search and rescue robots: from tragedy to technology. IEEE Intell. Syst. 17, 81–83. https://doi.org/10.1109/MIS.2002.999224.
- Davila Delgado, J.M., Oyedele, L., Ajayi, A., Akanbi, L., Akinade, O., Bilal, M., Owolabi, H., 2019. Robotics and automated systems in construction: understanding

- industry-specific challenges for adoption. J. Build. Eng. 26, 100868 https://doi.org/10.1016/j.jobe.2019.100868.
- Davtalab, O., Kazemian, A., Khoshnevis, B., 2018. Perspectives on a BIM-integrated software platform for robotic construction through Contour Crafting. Autom. Constr. 89, 13–23. https://doi.org/10.1016/j.autcon.2018.01.006.
- Dawod, M., Hanna, S., 2019. BIM-assisted object recognition for the on-site autonomous robotic assembly of discrete structures. Constr. Robot 3, 69–81. https://doi.org/ 10.1007/s41693-019-00021-9.
- Dembski, F., Wössner, U., Letzgus, M., Ruddat, M., Yamu, C., 2020. Urban digital twins for smart cities and citizens: the case study of Herrenberg, Germany. Sustainability 12, 2307. https://doi.org/10.3390/su12062307.
- Deng, M., Menassa, C.C., Kamat, V.R., 2021. From BIM to digital twins: a systematic review of the evolution of intelligent building representations in the AEC-FM industry. ITcon 26, 58–83. https://doi.org/10.36680/j.itcon.2021.005.
- P. Devadass, S. Stumm, S. Brell-Cokcan, Adaptive Haptically Informed Assembly with Mobile Robots in Unstructured Environments, in: Banff, AB, Canada, 2019. (htt ps://doi.org/10.22260/ISARC2019/0063).
- Ding, L., Jiang, W., Zhou, Y., Zhou, C., Liu, S., 2020. BIM-based task-level planning for robotic brick assembly through image-based 3D modeling. Adv. Eng. Inform. 43, 100993 https://doi.org/10.1016/j.aei.2019.100993.
- Du, G., Wang, K., Lian, S., Zhao, K., 2021. Vision-based robotic grasping from object localization, object pose estimation to grasp estimation for parallel grippers: a review. Artif. Intell. Rev. 54, 1677–1734. https://doi.org/10.1007/s10462-020-09888-5
- Dusty, Dusty Robotics | Construction robots | BIM-driven Layout, (n.d.). (https://www.dustyrobotics.com/).
- Emaminejad, N., Akhavian, R., 2022. Trustworthy AI and robotics: implications for the AEC industry. Autom. Constr. 139, 104298 https://doi.org/10.1016/j. cvtcs. 2023.104298
- Escamilla, E., Ostadalimakhmalbaf, M., Bigelow, B.F., 2016. Factors impacting hispanic high school students and how to best reach them for the careers in the construction industry. Int. J. Constr. Educ. Res. 12, 82–98. https://doi.org/10.1080/ 15578771.2015.1077296.
- Fan, J., Zheng, P., Li, S., 2022. Vision-based holistic scene understanding towards proactive human–robot collaboration. Robot. Comput. -Integr. Manuf. 75, 102304 https://doi.org/10.1016/j.rcim.2021.102304.
- Fang, Y., Cho, Y.K., Chen, J., 2016. A framework for real-time pro-active safety assistance for mobile crane lifting operations. Autom. Constr. 72, 367–379. https://doi.org/ 10.1016/j.autcon.2016.08.025.
- C. Feng, Camera Marker Networks for Pose Estimation and Scene Understanding in Construction Automation and Robotics., Thesis, 2015. (http://deepblue.lib.umich. edu/handle/2027.42/113481) (Accessed 23 April 2024).
- Feng, C., Kamat, V.R., 2013. Plane registration leveraged by global constraints for context-aware AEC applications. Comput. Aided Civ. Eng. 28, 325–343. https://doi. org/10.1111/j.1467-8667.2012.00795.x.
- Feng, C., Xiao, Y., Willette, A., McGee, W., Kamat, V.R., 2015. Vision guided autonomous robotic assembly and as-built scanning on unstructured construction sites. Autom. Constr. 59, 128–138. https://doi.org/10.1016/j.autcon.2015.06.002.
- Follini, C., Magnago, V., Freitag, K., Terzer, M., Marcher, C., Riedl, M., Giusti, A., Matt, D.T., 2020. BIM-integrated collaborative robotics for application in building construction and maintenance. Robotics 10, 2. https://doi.org/10.3390/ robotics10010002.
- Fu, B., Smith, W., Rizzo, D.M., Castanier, M., Ghaffari, M., Barton, K., 2023. Robust task scheduling for heterogeneous robot teams under capability uncertainty. IEEE Trans. Robot. 39, 1087–1105. https://doi.org/10.1109/TRO.2022.3216068.
- A. Golabchi, M. Akula, V.R. Kamat, Leveraging BIM for Automated Fault Detection in Operational Buildings, in: Montreal, Canada, 2013. (https://doi.org/10.22260/ISARC2013/0020)
- Grasshopper 3D, Wikipedia (2023). (https://en.wikipedia.org/w/index.php?title=Grasshopper_3D&oldid=1189175937) (Accessed 23 April 2024).
- Hentout, A., Aouache, M., Maoudj, A., Akli, I., 2019. Human–robot interaction in industrial collaborative robotics: a literature review of the decade 2008–2017. Adv. Robot. 33, 764–799. https://doi.org/10.1080/01691864.2019.1636714.
- 14:00-17:00, ISO 10218-1:2011, ISO (n.d.). (https://www.iso.org/standard/51330.html) (accessed April 24, 2024).
- Kamat, V.R., Martinez, J.C., 2000. 3D visualization of simulated construction operations. In: 2000 Winter Simulation Conference Proceedings (Cat. No.00CH37165). IEEE, Orlando, FL, USA, pp. 1933–1937. https://doi.org/10.1109/WSC.2000.899189.
- Kamat, V.R., Martinez, J.C., 2003. Automated generation of dynamic, operations level virtual construction scenarios. J. Inf. Technol. Constr. (ITcon) 8, 65–84.
- Kim, S., Chang, S., Castro-Lacouture, D., 2020. Dynamic modeling for analyzing impacts of skilled labor shortage on construction project management. J. Manag. Eng. 36, 04019035 https://doi.org/10.1061/(ASCE)ME.1943-5479.0000720.
- Kim, D., Kim, J., Lee, K., Park, C., Song, J., Kang, D., 2009. Excavator tele-operation system using a human arm. Autom. Constr. 18, 173–182. https://doi.org/10.1016/j. press. 2009.07.000.
- Kim, K., Park, J., Cho, C., 2020. Framework for automated generation of constructible steel erection sequences using structural information of static indeterminacy variation in BIM. KSCE J. Civ. Eng. 24, 3169–3178. https://doi.org/10.1007/ s12205-020-0163-6.
- Kim, S., Peavy, M., Huang, P.-C., Kim, K., 2021. Development of BIM-integrated construction robot task planning and simulation system. Autom. Constr. 127, 103720 https://doi.org/10.1016/j.autcon.2021.103720.
- Krogius, M., Haggenmiller, A., Olson, E., 2019. Flexible Layouts for Fiducial Tags. IEEE/ RSJ Int. Conf. Intell. Robots Syst. (IROS) 2019, 1898–1903. https://doi.org/ 10.1109/IROS40897.2019.8967787.

- S. Lee, J.I. Moon, Introduction of Human-Robot Cooperation Technologyat Construction Sites, in: Sydney, Australia, 2014. (https://doi.org/10.22260/ISARC2014/0134).
- Levine, S., Pastor, P., Krizhevsky, A., Ibarz, J., Quillen, D., 2018. Learning hand-eye coordination for robotic grasping with deep learning and large-scale data collection. Int. J. Robot. Res. 37, 421–436. https://doi.org/10.1177/0278364917710318.
- Li, R., Zou, Z., 2023. Enhancing construction robot learning for collaborative and long-horizon tasks using generative adversarial imitation learning. Adv. Eng. Inform. 58, 102140 https://doi.org/10.1016/j.aei.2023.102140.
- Liang, C.-J., Kamat, V.R., Menassa, C.C., McGee, W., 2022. Trajectory-based skill learning for overhead construction robots using generalized cylinders with orientation. J. Comput. Civ. Eng. 36, 04021036 https://doi.org/10.1061/(ASCE) CP.1943-5487.0001004.
- Liang, C.-J., McGee, W., Menassa, C.C., Kamat, V.R., 2022. Real-time state synchronization between physical construction robots and process-level digital twins. Constr. Robot 6, 57–73. https://doi.org/10.1007/s41693-022-00068-1.
- Liang, C.-J., McGee, W., Menassa, C.C., Kamat, V.R., 2022. Real-time state synchronization between physical construction robots and process-level digital twins. Constr. Robot 6, 57–73. https://doi.org/10.1007/s41693-022-00068-1.
- Liang, C.-J., Wang, X., Kamat, V.R., Menassa, C.C., 2021. Human–robot collaboration in construction: classification and research trends. J. Constr. Eng. Manag. 147, 03121006 https://doi.org/10.1061/(ASCE)CO.1943-7862.0002154.
- Liu, Y., Habibnezhad, M., Jebelli, H., 2021. Brain-computer interface for hands-free teleoperation of construction robots. Autom. Constr. 123, 103523 https://doi.org/ 10.1016/j.autcon.2020.103523.
- Lundeen, K.M., Dong, S., Fredricks, N., Akula, M., Seo, J., Kamat, V.R., 2016. Optical marker-based end effector pose estimation for articulated excavators. Autom. Constr. 65, 51–64. https://doi.org/10.1016/j.autcon.2016.02.003.
- Lundeen, K.M., Kamat, V.R., Menassa, C.C., McGee, W., 2017. Scene understanding for adaptive manipulation in robotized construction work. Autom. Constr. 82, 16–30. https://doi.org/10.1016/j.autcon.2017.06.022.
- Lundeen, K.M., Kamat, V.R., Menassa, C.C., McGee, W., 2019. Autonomous motion planning and task execution in geometrically adaptive robotized construction work. Autom. Constr. 100, 24–45. https://doi.org/10.1016/j.autcon.2018.12.020.
- Malik, A.A., Brem, A., 2021. Digital twins for collaborative robots: a case study in human-robot interaction. Robot. Comput. -Integr. Manuf. 68, 102092 https://doi. org/10.1016/j.rcim.2020.102092.
- Mantha, B.R.K., Jung, M.K., García De Soto, B., Menassa, C.C., Kamat, V.R., 2020. Generalized task allocation and route planning for robots with multiple depots in indoor building environments. Autom. Constr. 119, 103359 https://doi.org/ 10.1016/j.autcon.2020.103359.
- McClymonds, A., Asadi, S., Wagner, A., Leicht, R.M., 2022. Information Exchange for Supporting BIM to Robotic Construction. In: Construction Research Congress 2022. American Society of Civil Engineers, Arlington, Virginia, pp. 839–848. https://doi. org/10.1061/9780784483961.088.
- S. Meschini, Novel applications offered by integration of robotic tools in BIM-based design workflow for automation in construction processes, in: 2016. (https://mediatum.ub.tum.de/1484218) (Accessed 4 April 2024).
- NIBS, National BIM Standard-United States® Version 3 | National BIM Standard United States, (2015). (https://www.nationalbimstandard.org/nbims-us) (Accessed 22 March 2022).
- Park, J., Cho, Y.K., Martinez, D., 2016. A BIM and UWB integrated mobile robot navigation system for indoor position tracking applications. J. Constr. Eng. Proj. Manag. 6, 30–39. https://doi.org/10.6106/JCEPM.2016.6.2.030.
- Park, J., Cho, Y.K., 2022. Point cloud information modeling: deep learning-based automated information modeling framework for point cloud data. J. Constr. Eng. Manag. 148, 04021191 https://doi.org/10.1061/(ASCE)CO.1943-7862.0002227.
- Park, S., Wang, X., Menassa, C.C., Kamat, V.R., Chai, J.Y., 2024. Natural language instructions for intuitive human interaction with robotic assistants in field construction work. Autom. Constr. 161, 105345 https://doi.org/10.1016/j. autcon.2024.105345.
- Park, S., Yu, H., Menassa, C.C., Kamat, V.R., 2023. A comprehensive evaluation of factors influencing acceptance of robotic assistants in field construction work. J. Manag. Eng. 39, 04023010 https://doi.org/10.1061/JMENEA.MEENG-5227.
- Pérez, L., Diez, E., Usamentiaga, R., García, D.F., 2019. Industrial robot control and operator training using virtual reality interfaces. Comput. Ind. 109, 114–120. https://doi.org/10.1016/j.compind.2019.05.001.
- Pietroforte, R., 1997. Shop drawing process of stone veneered cladding systems.

 J. Archit. Eng. 3, 70–79. https://doi.org/10.1061/(ASCE)1076-0431(1997)3:2(70).
 Qian, K., Song, A., Bao, J., Zhang, H., 2012. Small teleoperated robot for nuclear
- Qian, K., Song, A., Bao, J., Zhang, H., 2012. Small teleoperated robot for nuclear radiation and chemical leak detection. Int. J. Adv. Robot. Syst. 9, 70. https://doi. org/10.5772/50720.
- $R.M.\& \stackrel{.}{Associates}, Rhino 7, \langle Www.Rhino 3d.Com \rangle \ (n.d.). \ \langle https://www.rhino 3d.com/7/\rangle \ (accessed April 23, 2024).$
- Robert McNeel & Associates, Rhino.Inside, \(\bar{Www.Rhino3d.Com}\) (2024). \(\bar{https://www.rhino3d.com/features/rhino-inside/\) (Accessed 11 January 2024).
- Rodrigues, P.B., Singh, R., Oytun, M., Adami, P., Woods, P.J., Becerik-Gerber, B., Soibelman, L., Copur-Gencturk, Y., Lucas, G.M., 2023. A multidimensional taxonomy for human-robot interaction in construction. Autom. Constr. 150, 104845 https:// doi.org/10.1016/j.autcon.2023.104845.
- Roldán, J.J., Peña-Tapia, E., Garzón-Ramos, D., de León, J., Garzón, M., del Cerro, J., Barrientos, A., 2019. Multi-robot Systems, Virtual Reality and ROS: Developing a New Generation of Operator Interfaces. In: Koubaa, A. (Ed.), Robot Operating System (ROS). Springer International Publishing, Cham, pp. 29–64. https://doi.org/ 10.1007/978-3-319-91590-6 2.

- S. Sharif, T.R. Gentry, L.M. Sweet, Human-Robot Collaboration for Creative and Integrated Design and Fabrication Processes, in: Auburn, AL, USA, 2016. (htt ps://doi.org/10.22260/ISARC2016/0072).
- She, L., Cheng, Y., Chai, J.Y., Jia, Y., Yang, S., Xi, N., 2014. Teaching Robots New Actions through Natural Language Instructions. In: The 23rd IEEE International Symposium on Robot and Human Interactive Communication. IEEE, Edinburgh, UK, pp. 868–873. https://doi.org/10.1109/ROMAN.2014.6926362.
- Siemens, GitHub ROS#, (2021). (https://github.com/siemens/ros-sharp).
- Suresh, A., Gaba, D., Bhambri, S., Laha, D., 2019. Intelligent Multi-fingered Dexterous Hand Using Virtual Reality (VR) and Robot Operating System (ROS). In: Kim, J.-H., Myung, H., Kim, J., Xu, W., Matson, E.T., Jung, J.-W., Choi, H.-L. (Eds.), Robot Intelligence Technology and Applications 5. Springer International Publishing, Cham, pp. 459–474. https://doi.org/10.1007/978-3-319-78452-6_37.
- Teizer, J., Blickle, A., King, T., Leitzbach, O., Guenther, D., Mattern, H., König, M., 2018.
 BIM for 3D Printing in Construction. In: Borrmann, A., König, M., Koch, C., Beetz, J.
 (Eds.), Building Information Modeling. Springer International Publishing, Cham,
 pp. 421–446. https://doi.org/10.1007/978-3-319-92862-3_26.
- Tsarouchi, P., Matthaiakis, A.-S., Makris, S., Chryssolouris, G., 2017. On a human-robot collaboration in an assembly cell. Int. J. Comput. Integr. Manuf. 30, 580–589. https://doi.org/10.1080/0951192X.2016.1187297.
- Volk, R., Stengel, J., Schultmann, F., 2014. Building Information Modeling (BIM) for existing buildings — literature review and future needs. Autom. Constr. 38, 109–127. https://doi.org/10.1016/j.autcon.2013.10.023.
- X. Wang, C.-J. Liang, C. Menassa, V. Kamat, Real-Time Process-Level Digital Twin for Collaborative Human-Robot Construction Work, in: Kitakyushu, Japan, 2020. (htt ps://doi.org/10.22260/ISARC2020/0212).
- Wang, X., Liang, C.-J., Menassa, C.C., Kamat, V.R., 2021. Interactive and immersive process-level digital twin for collaborative human-robot construction work. J. Comput. Civ. Eng. 35, 04021023 https://doi.org/10.1061/(ASCE)CP.1943-5487_0000988
- Wang, X., Wang, S., Menassa, C.C., Kamat, V.R., McGee, W., 2023. Automatic high-level motion sequencing methods for enabling multi-tasking construction robots. Autom. Constr. 155, 105071 https://doi.org/10.1016/j.autcon.2023.105071.

- Wong Chong, O., Zhang, J., Voyles, R.M., Min, B.-C., 2022. BIM-based simulation of construction robotics in the assembly process of wood frames. Autom. Constr. 137, 104194 https://doi.org/10.1016/j.autcon.2022.104194.
- Xu, L., Feng, C., Kamat, V.R., Menassa, C.C., 2019. An Occupancy Grid Mapping enhanced visual SLAM for real-time locating applications in indoor GPS-denied environments. Autom. Constr. 104, 230–245. https://doi.org/10.1016/j. autcon.2019.04.011.
- Yoon, S., Kim, Y., Park, M., Ahn, C.R., 2023. Effects of spatial characteristics on the human–robot communication using deictic gesture in construction. J. Constr. Eng. Manag. 149, 04023049 https://doi.org/10.1061/JCEMD4.COENG-12997.
- Yu, H., Kamat, V.R., Menassa, C.C., 2024. Cloud-based hierarchical imitation learning for scalable transfer of construction skills from human workers to assisting robots. J. Comput. Civ. Eng. 38, 04024019 https://doi.org/10.1061/JCCEE5.CPENG-5731.
- Yu, H., Kamat, V.R., Menassa, C.C., McGee, W., Guo, Y., Lee, H., 2023. Mutual physical state-aware object handover in full-contact collaborative human-robot construction work. Autom. Constr. 150, 104829 https://doi.org/10.1016/j.autcon.2023.104829.
- R. Zhang, S. Lee, M. Hwang, A. Hiranaka, C. Wang, W. Ai, J.J.R. Tan, S. Gupta, Y. Hao, G. Levine, R. Gao, A. Norcia, L. Fei-Fei, J. Wu, NOIR: Neural Signal Operated Intelligent Robots for Everyday Activities, (2023). (http://arxiv.org/abs/2311.01454) (accessed April 4, 2024).
- Zhang, Z., Lin, K.-Y., Lin, J.-H., 2023. 2SAFE: a health belief model-integrated framework for participatory ergonomics. Theor. Issues Ergon. Sci. 24, 281–298. https://doi.org/ 10.1080/1463922X.2022.2083716.
- Zhang, J., Luo, H., Xu, J., 2022. Towards fully BIM-enabled building automation and robotics: a perspective of lifecycle information flow. Comput. Ind. 135, 103570 https://doi.org/10.1016/j.compind.2021.103570.
- Zhou, T., Zhu, Q., Du, J., 2020. Intuitive robot teleoperation for civil engineering operations with virtual reality and deep learning scene reconstruction. Adv. Eng. Inform. 46, 101170 https://doi.org/10.1016/j.aei.2020.101170.
- Zhu, A., Pauwels, P., De Vries, B., 2021. Smart component-oriented method of construction robot coordination for prefabricated housing. Autom. Constr. 129, 103778 https://doi.org/10.1016/j.autcon.2021.103778.
- Zhu, Q., Zhou, T., Du, J., 2022. Upper-body haptic system for snake robot teleoperation in pipelines. Adv. Eng. Inform. 51, 101532 https://doi.org/10.1016/j. 2012.101532